

**SURVEY & REMONUMENTATION**

MAR 03 1998

\$7.00  
\$2.00

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 NOV 14 AM 9:00  
REG. OF DEEDS  
*Lucy Standa*

For corners in

Kent (County) Located in: Vergennes Township Corner Code #

|                                    |             |             |            |
|------------------------------------|-------------|-------------|------------|
| 1. Public Land Survey              | T <u>7N</u> | R <u>9W</u> | <u>A-8</u> |
|                                    | T _____     | R _____     | _____      |
|                                    | T _____     | R _____     | _____      |
|                                    | T _____     | R _____     | _____      |
| 2. Property Controlling in Section | S _____     | T _____     | R _____    |
|                                    | S _____     | T _____     | R _____    |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____     | R _____    |
|                                    | S _____     | T _____     | R _____    |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**10290**  
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on June 3 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

|     |      |                |                     |                                    |  |
|-----|------|----------------|---------------------|------------------------------------|--|
| A-8 | 1831 | G.L.O. Notes   | Mullett             | Set Post                           | P.A. 345 1990 KENT COUNTY<br>PEER APPROVED <u>8/28/97</u><br>CHAIRMAN <u>Randy Kolehouse</u><br>K.C. Monument (M-8, T7N, R10W) |
|     | 1956 | Witness Map    | K.C. Surveyor       | Iron                               |  |
|     | 1975 | L.C.R.C. #800  | Moore & Bruggink    | Iron                               |  |
|     | 1977 | L.C.R.C. #974  | Moore & Bruggink    | 3/4" Iron                          |  |
|     | 1981 | L.C.R.C. #1919 | Jonker Land Surveys | Fnd. 3/4" Iron / Set K.C. Monument |  |
|     | 1991 | L.C.R.C. #5824 | Exxel Engineering   | K.C. Monument                      |  |
|     | 1994 | L.C.R.C. #8053 | Glaza & Associates  | K.C. Monument (M-8, T7N, R10W)     |  |

Note: This corner is common with M-8, T7N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 7/17/81 and was recorded per L.C.R.C. #1919.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-8 Found a Standard Kent County Monument 2' ± North of the C/L of Mc Cabe Avenue (gravel) running East and West, 5' ± West of old fence row running North, and 180' ± East of the C/L of a bituminous drive running North to house #9575 per L.C.R.C.'s #1919, #5824, and #8053 as set by Rob Jonker in place of a 3/4" iron he found which checked L.C.R.C.'s #974, #800 and the K.C. Surveyor's records.

L.C.R.C. #1919

L.C.R.C. #8053

Remon. tag on SE side 15" Cherry N 37° E 39.08'  
Remon. tag on NE side 16" Oak S 33° E 35.18'  
Remon. tag on NE side 36" Oak N 22° W 36.00'  
Remon. tag on SW side 12" Cherry S 55° E 43.69'

Nail & K.C. remon tag in SE side 18" Cherry N 38° E 39.08'  
Nail & K.C. remon tag in NE side 18" Oak S 34° E 35.27' (m. 35.27')  
Nail & K.C. remon tag in NE side 38" Oak N 20° W 35.26' (m. 35.30')  
Nail & K.C. remon tag in SW side 12" Cherry S 54° E 43.73' (m. 43.77')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-8 Standard Kent County Monument

Nail & K.C. remon. tag on SE side 18" Cherry N 38° E 39.08'  
Nail & K.C. remon. tag on NE side 18" Oak S 34° E 35.27'  
Nail & K.C. remon. tag on NE side 38" Oak N 20° W 35.30'  
Nail & K.C. remon. tag on SW side 12" Cherry S 54° E 43.77'

Signed by Randy J. Kolehouse Date 9/23/97

EARTH TECH

Surveyor's Michigan License No. 25854

