

MAR 08 1999

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

REG. OF DEEDS

Lucy G. Smith

38 OCT 23 AM 9:56

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10748

Register of Deeds Stamp & File Number

For corners in

Kent (County)	Located in: Vergennes Township	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>9W</u>	<u>D-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on December 29 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1	Description	Set Corner
1975	L.C.R.C. #861 Medema, Van Kooten & Assoc.	"T" Iron / Set K.C. Monument
1985	L.C.R.C. #5165 R. Kolehouse	K.C. Monument
1994	L.C.R.C. #7096 Glaza & Associates	

Note: This corner is not common with D-13, T8N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by R. Kolehouse on 11/16/85 and was recorded per L.C.R.C. #5165.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Found a Standard Kent County Monument 3' South of the C/L of 4 Mile Road (gravel) running East and West on line of the remains of old fence line running South per L.C.R.C.'s #5165 and #7096 as set by Randy Kolehouse in place of a "T" iron he found which checked L.C.R.C. #861.

L.C.R.C. #5165

Nail & K.C. Remon. tag in S. Side 10" Ash S 75° E 60.97'
 Nail & K.C. Remon. tag in SW side 16" Maple S 50° E 48.40'
 Nail & K.C. Remon. tag in W. side 16" Beech S 05° E 78.87'
 Nail & K.C. Remon. tag in E. side 12" Elm S 15° W 43.73'
 S. end 15" C.M.P. S 20° W 13.8'
 N. end 15" C.M.P. N 15° W 17.7'

L.C.R.C. #7096

Nail & K.C. remon tag in S side 14" Ash S75°E 61.13' (m. 61.16')
 Nail & K.C. remon tag in SW side 22" Maple S50°E 48.54' (m. 48.56')
 Nail & K.C. remon tag in W side 18" Beech S05°E 78.64' (m. 78.63')
 Nail & K.C. remon tag in E side 20" Elm (dead) S15°W 43.63' (m. 43.62')
 South end 15" C.M.P. S20°W 13.9' (m. 14.41')
 North end 15" C.M.P. N15°W 18.9' (m. 18.88')
 K.C. mon. at the S 1/4 cor of Section 32, T8N, R9W West 94.32' (m. 94.21')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Standard Kent County Monument

Nail & K.C. remon. tag on S side 14" Ash S 75° E 61.16'
 Nail & K.C. remon. tag on SW side 22" Maple S 50° E 48.56'
 Nail & K.C. remon. tag on W side 18" Beech S 05° E 78.63'
 Nail & K.C. remon. tag on E side 20" Elm (dead) S 15° W 43.62'
 S end 18" cmp. S 20° W 14.41'
 N end 18" cmp. N 15° W 18.88'

C/L gravel road running E-W, North 3.0'
 On remains of old fence line running S
 K.C. Mon., D-13, T8N, R9W, West 94.21'

Signed by *Randy J. Kolehouse* Date _____

Surveyor's Michigan License No. 25854

