

\$7.00  
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

SECTION

For corners in

<u>Kent</u> (County)	Located in: Vergennes Township	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>9W</u>	<u>D-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 DEC 14 AM 8:00  
REG. OF DEEDS  
*Lucy Spauld*

10936

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 6 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-12 This corner was not originally set by the G.L.O.

1939	Witness Map	K.C. Surveyor	Concrete Monument
1978	L.C.R.C. #1169	Williams & Works	"T" Iron

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 8/20/98  
CHAIRMAN *Randy Kolehouse*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-12 Found a "T" iron 2.0' North of the C/L of Bennett Street (gravel) running East and West on line of a tree row running North and South per L.C.R.C. # 1169. Iron is 0.2' West of the intersection of 1/4 lines. Accepted iron as Center of Section.


K.C. Witness Map	L.C.R.C. #1169
24" Oak South 31.85' (m. 30.83')	18" Oak N.40°W. - 46.05' (m. 46.00')
	16" Oak N.25°W. - 26.90' (m. 26.84')
	36" Oak South - 30.80' (m. 30.83')
	14" Hickory N.60° E. - 57.75' (m. 57.77')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-12 Replaced "T" Iron with a Standard Kent County Monument

Nail & K.C. remon. tag on SW side 18" Oak N 40° W 46.00'  
 Nail & K.C. remon. tag on NE side 16" Oak N 25° W 26.84'  
 Nail & K.C. remon. tag on W side 36" Oak South 30.83'  
 Nail & K.C. remon. tag on SE side 14" Hickory N 60° E 57.77'  
 Nail & K.C. remon. tag on SE side 14" Oak N 81° E 65.50'  
 C/L of gravel road running E-W, South 2.0'  
 On tree row running N-S



Signed by Randy J. Kolehouse Date 11/18/98  
EARTH TECH  
Surveyor's Michigan License No. 25854