

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED  
 93 SEP 13 PM 2:00

For corners in  
Kent  
 (County)

Located In: VERGENNES TWP.  
 Corner Code //

1. Public Land Survey

T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
 in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S 9 T 7N R 9W F-4

3. Miscellaneous  
 Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_

Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REG. OF DEEDS

6842

(Register of Deeds Stamp & File Number)

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   |    |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Douglas W. Bonnema, in a field survey on August 27, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Nothing in available records at County Register of Deeds or at County Surveyor.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set Kent County Mon. (Harrison) at the intersection of the 1/4 lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Kent County Harrison Mon. (4"x30")

Tree row to North is West 84.0'  
 Set nail & tag in S sde 14" Hickory N60°W 91.45'  
 Set PK & tag in E sde P. Serv. Pole N3°W 304.30'  
 Set PK & tag in W sde P. Pole S4°E 55.39'  
 C/L of large stone (painted red) S7°E 34.2'  
 Set nail & tag in N sde 14" Hickory S53°E 53.60'  
 Set nail & tag in NW sde 12" Apple N52°E 42.56'  
 Tree row to South is 0' East  
 N-S power line East 1'  
 C/L E-W gravel North 1'

Signed by Douglas W. Bonnema

Date September 7, 1993

Surveyor's Michigan License No. 12579

