

SURVEY & REMONUMENTATION

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

KENT COUNTY REMONUMENTATION

For corners in

SECTION

Kent
(County)

Located in: Vergennes
Township

Corner Code #

1. Public Land Survey	T 7N	R 9W	F-6
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 16 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-6	This corner was not originally set by the G.L.O.			
1937	Witness Map	K.C. Surveyor	2" Iron	P.A. 345 1990 KENT COUNTY
1972	L.C.R.C. #399	Williams & Works	X Cut on Rock	PEER APPROVED 10/22/98
1994	Cert. Survey L. 263 P. 47	Exxel Engineering	Iron Stake	CHAIRMAN <u>Harry Kubers</u>

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-6 Did not find 8" stone shown in L.C.R.C. #399. Set a point using witnesses from Cert. Survey L. 263 P. 47 and L.C.R.C. #399. This point is 2.6' East and 0.3' North of the intersection of 1/4 lines. Accepted as Center of Section.

Cert. Survey L. 263 P. 47

L.C.R.C. #399

Nail in NE sde 15" Walnut S 60° W 10.12'
Dbl. Head nail in W sde 8" Ash N 10° E 13.05'
Dbl. Head nail in S sde 20" Walnut East 66.91'
Dbl. Head nail in N sde 26" Walnut West 20.32'

24" Walnut W 20.51'
12" Walnut S60°W 9.90'
20" Walnut S70°E 63.89'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-6 Set a Standard Kent County Monument

Nail & K.C. remon. tag on S side 18" Walnut S 60° W 10.20'
Nail & K.C. remon. tag on W side 10" Ash S 20° E 31.43'
Nail & K.C. remon. tag on N side 26" Walnut West 20.39'
Nail & K.C. remon. tag on W side 10" Ash N 00° E 12.87'
Nail & K.C. remon. tag on N side 8" Ash S 80° E 24.93'
Dbl. headed nail on S side 20" Walnut East 66.88'
Double fence line running E-W, North 25' ±
Fence line running N-S, East 40' ±

Signed by Randy J. Kolehouse

Date 11/18/98

EARTH TECH

Surveyor's Michigan License No. 25854

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 DEC 14 AM 8:00
REG. OF DEEDS
Lucy St. Grand

10939

Register of Deeds Stamp & File Number

