

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

97 APR 29 AM 8:28

For corners in **SECTION**
KENT COUNTY

Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>9W</u> G-13
	T _____ R _____
	T _____ R _____
	T _____ R _____
2. Property Controlling in Section	S _____ T _____ R _____
	S _____ T _____ R _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____
	S _____ T _____ R _____

REG. OF DEEDS

9903

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 6, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-13	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		3/4" Iron on Leaded Stone
	1984	LCRC #3878	Stadt	Iron in Mon. Box
	1985	LCRC #4165	Rosema	Set Kent County Monument in Mon. Box
	1991	LCRC #5796	Unema	Kent County Monument in Mon. Box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 4/1/85 and was recorded per LCRC #4165.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema in place of the 1/2" Iron Pipe he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC #3878.

LCRC #4165	LCRC #5796
Nail & tag curb joint N62°W 83.65'	Nail & tag 6" Locust S46°E 67.17'
PK Nail & tag curb joint S02°W 23.22'	Nail & tag curb joint N62°W 83.62'
Nail & tag 20" Locust N35°E 55.42'	Nail & tag 22" Locust N36°E 55.45'
Nail & tag Tw. 10" Locust S63°E 123.73'	PK Nail & tag curb joint S02°W 23.20'
KC Mon. (G-1, T6N, R9W) West 90.00'	KC Mon. (G-1, T6N, R9W) West 89.98'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag SW side 8" Locust	S46°E 67.17'
Nail & KC Remon. tag W. side 24" Locust	N36°E 55.45'
Nail & KC Remon. tag W. side Guy Pole	N10°W 45.84'
Nail & KC Remon. tag W. side P. Pole	S05°W 74.22'
Kent Co. Mon. (G-1, T6N, R9W)	West 89.98'
Mon. on C/L E-W blacktop road	
Mon. is 44'± E. of C/L N-S blacktop road	



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN Harry Habel