

FORM 08 1999

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

REG. OF DEEDS

*Lucy Bond*

98 OCT 23 AM 9:57

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

For corners in

Kent (County)	Located in: Vergennes Township	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>9W</u>	<u>H-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10781

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 7 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1 This corner was not originally set by the G.L.O.

1985	L.C.R.C. #5163	R. Kolehouse	Fnd. 3" Iron / Set K.C. Monument
1991	L.C.R.C. #5916	William Byl	K.C. Monument

Note: This corner is not common with H-13, T8N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse on 11/23/85 and was recorded per L.C.R.C. #5163.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1 Found a Standard Kent County Monument at the C/L of 4 Mile Road (bit.) running East and West, on line of a tree row running North and South and a fence line running North, per L.C.R.C.'s #5163 and #5916 as set by R. Kolehouse in place of a 3" iron he found.

L.C.R.C. #5163

Nail & K.C. Remon. tag in NW side tw 4" Wild Cherry S 25° W 25.82'  
Nail & K.C. Remon. tag in N. side 8" Oak S 65° W 82.20'  
Nail & K.C. Remon. tag in SW side 16" Hickory N 40° W 36.05'  
Nail & K.C. Remon. tag in S. side 16" Hickory N 65° W 85.75'

L.C.R.C. #5916

Nail & KC Remon. tag N. side 4-12" W. Cherry S55°E 79.21' (m. 79.20')  
Nail & KC Remon. tag NW side Tw. 4" W. Cherry S25°W 28.58' (m. 28.71')  
Nail & KC Remon. tag N. side 12" Oak S65°W 81.14' (m. 81.33')  
Nail & KC Remon. tag SW side 20" Hickory N40°W 35.73' (m. 35.80')  
Nail & KC Remon. tag S. side 20" Hickory N65°W 84.67' (m. 84.76')  
Nail & KC Remon. tag W. side P. Pole S10°W 54.17' (m. 54.20')  
Kent County Mon. @ S ¼ cor. Sec. 34, T8N, R9W S90°W 6.38'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1 Standard Kent County Monument

Nail & K.C. remon. tag on S side 4-12" W. Cherry S 55° E 79.20'  
Nail & K.C. remon. tag on NW side twin 4" W. Cherry S 25° W 28.71'  
Nail & K.C. remon. tag on N side 12" Oak S 65° W 81.33'  
Nail & K.C. remon. tag on SW side 20" Hickory N 40° W 35.80'  
Nail & K.C. remon. tag on S side 20" Hickory N 65° W 84.76'  
Nail & K.C. remon. tag on W side P. pole S 10° W 54.20'

On tree row running N-S  
On fence line running N  
K.C. Mon., H-13, T8N, R9W, West 6.38'

Signed by *Randy J Kolehouse*  
EARTH TECH

Date \_\_\_\_\_

Surveyor's Michigan License No. 25854

