PERCITOR OF PRINCIPLE OF PRINCI

| \$7.00 | |
|--------|--|
| \$2.00 | |

For corners in

THE H 3 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

| ~ . | | | , | |
|------|--------|--------|-----------|----|
| KENT | COUNTY | REMONU | JMENTATIO | ΛC |

| | Kent | Located in: Vergennes | Corner Code # |
|----|----------------------|-------------------------|---------------|
| | (County) | Township | |
| 1. | Public Land Survey | T <u>7N</u> R <u>9W</u> | <u>J-6</u> |
| | | T R | |
| | | T R | |
| | | T R | |
| 2. | Property Controlling | S T R | |
| | in Section | S T R | |
| 3. | Miscellaneous | STR | |
| | Property in Sec. | S T R | |

STATE OF MICHALLA COUNTY OF MENT PRECEIVED FOR RECORD 98 DEC 14 AM 8: 00 REG. OF DEEDS

11027

Register of Deeds Stamp & File Number

4. Lot No.______, Recorded Plat ______


5. Private Claims _____

I, Randy Kolehouse, in a field survey on August 5 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- J-6 This corner was not originally set by the G.L.O.

No information on record for this corner.



P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN Frug futer

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- J-6 Found a capped iron #31604 on an old fence line running East and South, an old fence remnant running West and a tree row running North and West. Iron is 0.3' South and 0.6' West of the intersection of 1/4 lines. Accepted iron as Center of Section.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- J-6 Replaced Capped Iron with a Standard Kent County Monument

Nail & K.C. remon. tag on W side 14" Maple N 30° E 7.50'

Nail & K.C. remon. tag on S side 22" Maple S 60° E 15.38'

Nail & K.C. remon. tag on E side 8" Cherry Due S 13.50'

Nail & K.C. remon. tag on N side 8" Ash S 80° W 23.88'

On fence running E-S

On fence remnant running W

On tree row running N-W

RANDY J.
KOLEHOUSE
LAND
SURVEYOR
NO.
25854

Signed by_

EARTH FEC

Date ___

2/4/98

Surveyor's Michigan License No.

25854