

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION _____

For corners in

Kent (County)	Located in: Vergennes Township	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>9W</u>	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 98 OCT 23 AM 9:58
 REG. OF DEEDS
[Signature]

10802

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 7 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A.	Description of original monument and accessories and/or subsequent restoration:
K-1	1837 G.L.O. Notes N. Brookfield Set Post
	1981 L.C.R.C. #2314 Nederveld & Jonker "T" Iron
	1986 L.C.R.C. #4359 Kolehouse Fnd. "T" Iron / Set K.C. Monument
	1991 L.C.R.C. #5919 William Byl K.C. Monument

Note: This corner is not common with K-13, T8N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse on 11/23/85 and was recorded per L.C.R.C. #4359.

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 2/19/98
 CHAIRMAN *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found a Standard Kent County Monument on the C/L of 4 Mile Road (gravel) running East and West, 17' East of the C/L of Ashley Road (gravel) running North, and 10' East of the C/L of Ashley Road (gravel) running South per L.C.R.C.'s #4359 and #5919 as set by Randy Kolehouse in place of a "T" iron he found 24.42' East of a K.C. Monument at the SW corner of Sec. 36, T8N, R9W, which checked L.C.R.C. #2314.

L.C.R.C. #4359

L.C.R.C. #5919

Nail & K.C. Remon. tag in S. side 12" Maple N 75° E 130.65'	Nail & KC Remon. tag S. side 14" Maple N75°E 130.77' (m. 130.81')
Nail & K.C. Remon. tag in N. side P. Pole S 50° E 75.00'	Nail & KC Remon. tag N. side P. Pole S50°E 75.14' (m. 75.16')
Top C/L tele. riser S 45° W 67.5'	Top C/L tele. riser S45°W 67.42' (m. 67.17')
Top C/L S. end 15" Conc. culv. S 80° E 104.6'	Top C/L S. end 15" conc. culv. S80°E 104.60' (m. 104.50')
K.C. Monument at the SW cor. sec. 36 T8N R9W., West 24.42'	Kent County Monument @ SW cor. Sec. 36, T8N, R9W S90°W 24.40' (m. 24.46')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1	Standard Kent County Monument
Nail & K.C. remon. tag on NW side P. pole N 13° E 205.18'	On C/L gravel road running E-W
Nail & K.C. remon. tag on SE side P. pole S 60° W 192.12'	C/L gravel road running N, West 17.0'
Nail & K.C. remon. tag on S side 14" Maple N 75° E 130.81'	C/L gravel road running S, West 10.0'
Nail & K.C. remon. tag on N side P. pole S 50° E 75.16'	K.C. Mon., K-13, T8N, R9W, S 90° W 24.46'
Top C/L MBT box S 45° W 67.17'	
Top C/L S. end 15" conc. culvert S 80° E 104.50'	

Signed by *[Signature]*
 EARTH TECH
 Surveyor's Michigan License No. 25854

