

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
98 DEC 14 AM 8:00
REG. OF DEEDS
Lucy St. Paul

For corners in

SECTION

Kent (County)	Located in: Vergennes Township	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>9W</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

10949
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on September 8 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-3	1837	G.L.O. Notes	N. Brookfield	Set Post
	1877	Notes	Ionia Co. Witness Book	N/A
	1990	L.C.R.C. #5313	T. Chettleburgh	Fnd. Stones in Ring / Set K.C. Mon. in Center of Stones
	1995	L.C.R.C. #8277	William Byl	K.C. Monument P.A. 345 1990 KENT COUNTY

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Note: This corner is common with A-3, T7N, R8W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by T. Chettleburgh on 2/5/90 and was recorded per L.C.R.C. #5313.

PEER APPROVED 9/24/98
CHAIRMAN Randy Kolehouse

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 Found a Standard Kent County Monument in woods per L.C.R.C.'s #5313 and #8277 as set by T. Chettleburgh in the center of stones he found which checked notes from the Ionia County witness book. No occupation lines were visible.

L.C.R.C. #5313

L.C.R.C. #8277

Nail & KC Remon tag in SE side of 20" B. Oak N 19° E 16.13'
 Nail & KC Remon tag in N. side of 18" B. Oak S 89° E 40.92'
 Nail & KC Remon tag in NE side of 12" Oak S 49° E 26.98'
 Nail & KC Remon tag in SE side of 12" W. Oak S 23° W 24.15'
 Nail & KC Remon tag in NW side of 14" W. Oak S 56° W 10.71'
 10.71')
 Nail & KC Remon tag in NE side of 15" W. Oak N 68° W 12.44'


Nail & KC Remon. tag SE side of 22" B. Oak N 19° E 16.13' (m. 16.13')
 Nail & KC Remon. tag N. side of 20" B. Oak S 89° E 40.92' (m. 40.94')
 Nail & KC Remon. tag NE side of 14" Oak S 49° E 26.98' (m. 27.00')
 Nail & KC Remon. tag, SE side of 14" W. Oak S 23° W 24.15' (m. 24.16')
 Nail & KC Remon. tag NW side of 14" W. Oak S 56° W 10.71' (m. 10.71')
 Nail & KC Remon. tag NE side of 15" W. Oak N 68° W 12.44' (m. 12.46')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 Standard Kent County Monument

Nail & K.C. remon. tag on SE side of 22" B. Oak N 20° E 16.13'
 Nail & K.C. remon. tag on N. side of 20" B. Oak S 88° E 40.94'
 Nail & K.C. remon. tag on NE side of 14" Oak S 51° E 27.00'
 Nail & K.C. remon. tag on SE side of 14" W. Oak S 25° W 24.16'
 Nail & K.C. remon. tag on NW side of 14" W. Oak S 60° W 10.71'
 Nail & K.C. remon. tag on NE side of 15" W. Oak N 65° W 12.46'



Signed by Randy J. Kolehouse
EARTH TECH

Date 11/18/98

Surveyor's Michigan License No. 25854