

REMONUMENTATION  
 \$7.00  
 \$2.00  
 MAR 08 1999

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
 KENT COUNTY REMONUMENTATION

For corners in SECTION

Kent (County)	Located in:	Vergennes Township	Corner Code #
1. Public Land Survey	T <u>7N</u>	R <u>9W</u>	<u>M-9</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 99 OCT 23 AM 9:58  
 REG. OF DEEDS  
*Luigi Standa*

10823  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 9 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-9	1837	G.L.O. Notes	N. Brookfield	Set Post
	1973	L.C.R.C. #538	Williams & Works	Iron at Stone
	1981	L.C.R.C. #1999	Jonker Land Survey	Fnd. "T" Iron / Set K.C. Monument
	1995	L.C.R.C. #8283	William Byl	K.C. Monument

Note: This corner is common with A-9, T7N, R8W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 8/11/81 and was recorded per L.C.R.C. #1999.

345 1990 KENT COUNTY  
 PEER APPROVED 2/19/98  
 CHAIRMAN Randy Kolehouse

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found a Standard Kent County Monument 170' ± East of the C/L of Montcalm Avenue (gravel) running South and Northwesterly, on top of steep hill, on line of a tree row running Easterly per L.C.R.C.'s #1999 and #8283 as set by Rob Jonker in place of a "T" iron he found by a stone which checked L.C.R.C. #538.

L.C.R.C. #1999

L.C.R.C. #8283

- Remon. tag on NW side 10" Walnut N32°E 11.13'
- Remon. tag on N side 15" Tr/Oak S80°E 36.25'
- Remon. tag on W side 10" Tr. Oak S02°E 18.52'
- Remon. tag on SW side 10" Tw. Oak N50°W 28.24'

- Nail & KC Remon. tag NW side 10" Walnut (dead) N32°E 11.21' (m. 11.13')
- Nail & KC Remon. tag N. side 18" Tri. Oak S80°E 36.10' (m. 36.08')
- Nail & KC Remon. tag W. side 14" Tri. Oak S02°E 19.05'
- Nail & KC Remon. tag SW side 14" Tw. Oak N50°W 28.10' (m. 28.05')
- Nail & KC Remon. tag W. side 24" Tw. Oak N15°E 33.08' (m. 33.19')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Standard Kent County Monument

- Nail & K.C. remon. tag on NW side 10" dead Walnut N 32° E 11.13'
- Nail & K.C. remon. tag on N side 18" Tri. Oak S 80° E 36.08'
- Nail & K.C. remon. tag on W side 14" Tri. Oak S 02° E 19.05'
- Nail & K.C. remon. tag on SW side 14" Twin Oak N 50° W 28.05'
- Nail & K.C. remon. tag on W side 28" Twin Oak N 15° E 33.19'
- On line of tree row running East
- C/L of gravel road running South and Northwesterly, West 170' +



Signed by Randy J. Kolehouse  
 EARTH TECH

Date 9-1-98

Surveyor's Michigan License No. 25854