

\$7.00
\$2.00

MAR 08 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 OCT 23 AM 9:58

REG. OF DEEDS
Lucy Bond

10824

Register of Deeds Stamp & File Number

For corners in Kent (County) Located in: Vergennes Township Corner Code #

1. Public Land Survey T 7N R 9W M-10

2. Property Controlling in Section S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 8 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-10 1837	G.L.O. Notes	N. Brookfield	Set Post
1977	L.C.R.C. #1062	Williams & Works	Iron in Monument Box
1981	L.C.R.C. #2000	Jonker Land Survey	Fnd. Boat Spike / Set K.C. Monument in Mon. Box
1995	L.C.R.C. #8284	William Byl	K.C. Monument

Note: This corner is common with A-10, T7N, R8W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 8/11/81 and was recorded per L.C.R.C. #2000.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/19/98
CHAIRMAN Randy Kolehouse

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found a Standard Kent County Monument at the C/L intersection of Flat River Drive (bit.) running East and West and Montcalm Avenue (bit.) running North and South per L.C.R.C.'s #2000 and #8284 as set by Rob Jonker in place of a boat spike he found in a monument box which checked L.C.R.C. #1062.

L.C.R.C. #2000	L.C.R.C. #8284
Remon. tag on NW side 36" Oak N50°E 49.40'	Nail & KC Remon. tag NW side 42" Oak N50°E 49.28'
Remon. tag on S side 14" Oak N76°W 102.38'	Nail & KC Remon. tag W. side 42" Oak S30°E 56.40' (m. 56.27')
C/L B.T. South 1.5'	Nail & KC Remon. tag E. side 18" Oak S20°W 112.15' (m. 112.23')
	Nail & KC Remon. tag NW side 14" Pine S70°W 118.40'
	Nail & KC Remon. tag E. side 28" Oak N20°W 81.22' (m. 81.27')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate location of the corner:

M-10 Standard Kent County Monument

Nail & K.C. remon. tag on NW side 42" Oak N 50° E 49.28'

Nail & K.C. remon. tag on W side 42" Oak S 30° E 56.27'

Nail & K.C. remon. tag on E side 18" Oak S 20° W 112.23'

Nail & K.C. remon. tag on NW side 14" Pine S 70° W 118.40'

Nail & K.C. remon. tag on E side 28" Oak N 20° W 81.27'

On C/L "X" of bit. roads running N-S & E-W



Signed by Randy J. Kolehouse Date 9-1-98

Surveyor's Michigan License No. 25854