

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 94 DEC 28 PM 3:04

For corners in

<u>Kent</u>	Located In:	Corner Code #:
(County)		
Ada Township		
1. Public Land Survey	T <u>7N</u> R <u>10W</u>	<u>D-12</u>
	T _____ R _____	<u>Center</u>
	T _____ R _____	<u>Section 32</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Lee J. Bond
 REG. OF DEEDS

7931

Register of Deeds Stamp & File Number

Thomas W. Chettleburgh, in a field survey on December 14, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- Corner Post not set by U.S. Government Land Surveys
- Williams & Works 1944 Set center from witnesses
 - Williams & Works 1953 Reset center from witnesses
 - Williams & Works 1956 Held corner as witnessed above
 - Williams & Works 1968 Held corner as witnessed above
 - Exxel 1981 Held above corner, recorded L.C.R.C. #1545

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Find 3/4" iron pipe from above witnesses
- 3/4" iron pipe is 2.75' N & 5.30' E of intersection of 1/4 lines
- Replaced 3/4" iron pipe with 4"X30" Harrison Monument

The location of the 3/4" iron pipe above is accepted by me and is generally accepted by Professional Surveyors as the best position of the corner based on the available evidence.

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 12/15/94
 CHAIRMAN *Harry Kubel*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 4"X30" Harrison Monument
- | | | | | |
|--|---------|------------|-----------|--------|
| Nail/tag | E side | 26" Walnut | Due North | 25.45' |
| Centerline hydrant | | | N30°E | 24.82' |
| Nail/tag | SE side | Power Pole | N55°E | 52.32' |
| Nail/tag | NE side | 13" Elm | S42°E | 46.34' |
| Nail/tag | SW side | 14" Elm | N60°W | 40.50' |
| Centerline East-West pavement, Ada Drive | | | South | 11.5' |



Signed by *Thomas W. Chettleburgh* Date December 27, 1994
 Surveyor's Michigan License No. 16036