

# SURVEY & REMONUMENTATION

MAR 03 1998

## SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

For corners in

Kent  
(County)

Located in: Ada Township

Corner Code #

- |                                    |             |              |            |
|------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey              | T <u>7N</u> | R <u>10W</u> | <u>E-2</u> |
|                                    | T _____     | R _____      | _____      |
|                                    | T _____     | R _____      | _____      |
|                                    | T _____     | R _____      | _____      |
| 2. Property Controlling in Section | S _____     | T _____      | R _____    |
|                                    | S _____     | T _____      | R _____    |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____      | R _____    |
|                                    | S _____     | T _____      | R _____    |

REG. OF DEEDS

*Handwritten signature*

97 OCT 15 AM 8:50

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

10186

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on April 10 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E-2	1831	G.L.O. Notes	Mullett	Set Post
	1935-64	Witness Map	K.C. Surveyor	Iron & Stone
	1973	L.C.R.C. #551	Medema, Van Kooten & Assoc.	3/4" Iron in Concrete
	1974	L.C.R.C. #727	Medema, Van Kooten & Assoc.	3/4" Iron in Concrete
	1981	L.C.R.C. #2552	J. Bueche	Fnd. Concrete Monument / Set K.C. Monument
	1989	L.C.R.C. #5126	T. Chettleburgh	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by J. Bueche on 12/14/81 and was recorded per L.C.R.C. #2552.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E-2 Found a Standard Kent County Monument at the C/L of Egypt Valley Avenue (bit.) running North and South on line of fence line running East per L.C.R.C.'s #2552 and #5126 as set by J. Bueche in place of a concrete monument he found 24" down which checked L.C.R.C.'s #727, #551 and the K.C. Surveyor's records.

L.C.R.C. #2552

L.C.R.C. #5126

NW cor. stone pillar N 90° E 30.30'  
K. C. Remon. tag & nail in East side 10" Hickory N 35° W 73.70'  
K. C. Remon. tag & nail in South side 10" Hickory N 90° W 28.32'  
K. C. Remon. tag & nail in West side 24" Oak S 25° E 80.20'

Northwest corner stone pillar S 83° E 30.22'  
K.C. Remon. Tag & Nail NE side 24" Hickory S 58° E 38.12'  
K.C. Remon. Tag & Nail West side 29" Oak S 24° E 80.08' (m. 80.10')  
K.C. Remon. Tag & Nail SE side 11" Walnut S 40° W 57.17' (m. 57.25')  
K.C. Remon. Tag & Nail South side 10" Hickory S 89° W 28.32'  
K.C. Remon. Tag & Nail East side 11" Hickory N 31° W 73.67'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-2 Standard Kent County Monument

NW cor. stone pillar S 83° E 30.22'  
Nail & K.C. remon. tag on NE side 24" Hickory S 58° E 38.12'  
Nail & K.C. remon. tag on W side 30" Oak S 24 E 80.10'  
Nail & K.C. remon. tag on SE side 12" Walnut S 40° W 57.25'  
Nail & K.C. remon. tag on S side 10" Hickory S 89° W 28.32'  
Nail & K.C. remon. tag on E side 12" Hickory N 31° W 73.67'

Signed by Randy J. Kolehouse Date 8-1-97  
EARTH TECH

Surveyor's Michigan License No. 25854

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 5/22/97  
CHAIRMAN Handwritten signature

