

SURVEY & REMONUMENTATION

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Ada Township	Corner Code #
1. Public Land Survey	T <u>7N</u>	R <u>10W</u>	<u>G-1</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous	S _____	T _____	R _____
Property in Sec.	S _____	T _____	R _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 OCT 15 AM 8:50
 REG. OF DEEDS
Lucy Bond

10200

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on April 10 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Date	Description	Surveyor	Notes
G-1 1831	G.L.O. Notes	Mullett	Set Post
1964	Witness Map	K.C. Surveyor	Iron
1972	Notes	Exxel Engineering	"T" Iron
1974	L.C.R.C. #725	Medema, Van Kooten & Assoc.	"T" Iron
1984	L.C.R.C. #3965	Exxel Engineering	Fnd. "T" Iron / Set K.C. Monument
1991	L.C.R.C. #6267	Chris Marschall	K.C. Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 5/22/97
 CHAIRMAN Harry Huber

Note: This corner is not common with G-13, T8N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 9/27/84 and was recorded per L.C.R.C. #3965.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Found a Standard Kent County Monument on the Township line 6' South of the C/L of 4 Mile Road (gravel) running East and West and the C/L of Dursam Road (abandoned) running South per L.C.R.C.'s #3965 and #6267 as set by Exxel Engineering in place of a "T" iron they found 0.27' North of the Township line which checked L.C.R.C. #725, the 1972 notes of Exxel Engineering, and the K.C. Surveyor's records.

L.C.R.C. #3965

L.C.R.C. #6267

C.I. mon. at SE corner Section 33, T8N, R10W East 277.20'	Nail & Tag S sd. Tw. 10"-4" Oak N 65 W 106.37' (m. 106.45')
Nail & remon tag in N sde 28" Oak S 65° W 28.43'	Nail & Tag N sd. 30" Oak S 70 W 28.41'
Nail & remon tag in SW sde 18" Oak N 20° W 39.14'	Nail & Tag SW sd. 12" Oak N 30 W 39.08' (m. 39.13')
Nail & remon tag in SW sde 10" Oak S 13° E 93.35'	Nail & Tag W side 12" Oak S 40 E 93.35'
& E-W gravel road North 5' ±	1/4 cor. G-13 Due East 277.27'
	On C/L of abandon road to the South

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Standard Kent County Monument

- Nail & K.C. remon. tag on N side 30" Oak S 70° W 28.41'
- Nail & K.C. remon. tag on SW side 12" Oak N 30° W 39.13'
- Nail & K.C. remon. tag on W side 12" Oak S 40° E 93.35'
- Nail & K.C. remon. tag on S side 12" Oak N 65° W 106.45'
- Mon. East 277.27'
- K.C. Mon., G-13, T8N, R10W, East 277.27'



Signed by Randy J. Kolehouse Date 8-1-97
 EARTH TECH

Surveyor's Michigan License No. 25854