

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00  
MAR 03 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 NOV 14 AM 9:01  
REG. OF DEEDS  
*Eric Bond*

For corners in **SECTION**

Kent (County)	Located in: Ada Township	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>10W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**10313**

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on August 5 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-11	1831	G.L.O. Notes	Mullett	Set Post
	N/A	Witness Map	K.C. Surveyor	Iron & Stone
	1971	L.C.R.C. #19	J. Spencer	"T" Iron
	1974	L.C.R.C. #736	W. Smith	"T" Iron
	1982	L.C.R.C. #2713	Williams & Works	"T" Iron (to correct L.C.R.C. #386 recorded 4/3/72)
	1981	L.C.R.C. #2586	Jonker Land Survey	Fnd. "T" Iron / Set K.C. Monument
	1989	L.C.R.C. #5151	T. Chettleburgh	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 12/28/81 and was recorded per L.C.R.C. #2586.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11 Found a Standard Kent County Monument 55' North of the C/L of Headley Street running East and West and 18' West of the West face of a brick building per L.C.R.C.'s #2586 and #5151 as set by Rob Jonker in place of a "T" iron he found at grade over a large stone 29" below grade which checked L.C.R.C.'s #2713, #736, #19, and the K.C. Surveyor's records.

L.C.R.C. #2586

L.C.R.C. #5151

SW corner bldg. fnd. S43°E 24.78'	Northwest corner building (corner brick) N 08° E 104.87' (m. 104.9')
Perpendicular face of brick bldg. S88°E m/l 18.04'	Perpendicular face of brick building S 86° E 18.06'
SE corner bldg. fnd. N74°W 129.57'	Southwest corner building foundation S 40° E 24.76'
C/L top Hyd. #130 S57°W 58.91'	K.C. Remon. Tag & Nail West side 18" Maple S 05° E 108.17' (m. 108.23')
	Centerline top Hydrant #130 S 60° W 58.90' (m. 59.0')
	Southeast corner building foundation N 71° W 129.47' (m. 129.58')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 Standard Kent County Monument

- NW cor. brick bldg. at foundation N 17° E 104.9'
- SW cor. brick bldg. S 39° E 24.76'
- Nail & K.C. remon. tag on W side 28" Maple S 03° E 108.23'
- C/L top hydrant (behind Tri. Box Elder) S 61° W 59.0'
- SE cor. bldg. foundation N 70° W 129.58'

Signed by *Randy J. Kolehouse* Date 9/23/97

EARTH TECH

Surveyor's Michigan License No. 25854

