

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 7N R 10W H-13
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 SEP 13 PM 12:03
 REG. OF DEEDS
Lucy Bond

9342

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on June 13, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1831	GLO	Mullett	Set Post
	1956	Kent Co. Wit.		Iron
	1978	LCRC #1215	Bonnema	1" Iron
	1981	LCRC #1767	Merdzinski	Set Kent County Monument
	1994	LCRC #8065	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 8/22/96
 CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/29/81 and was recorded per LCRC #1767

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Iron 4' long he found. Said Iron checks with Kent Co. Wit. and LCRC #1215.

LCRC #1767 (Nail/tag in trees)

LCRC #8065 (Nail/tag in trees)

20" Tri. Cherry S50°W 77.66'	6" Tw. Box Elder S85°E 7.69'
4" Oak S65°W 46.00' 8" Apple N30°W 65.48'	SW cor. gar. fnd. N65°E 78.38'
12" Tw. Box Elder S75°W 52.75'	KC Monument West 63.68'
6" Tw. Box Elder S85°E 7.63'	14" Quint. Tree N13°E 52.04'
KC Mon. West 63.68' SW cor. gar. N65°E 78.38'	10" Box Elder S15°W 0.83'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument	
Nail & KC Remon. tag S. side Tri. 10" Box Elder	S85°E 7.69'
New Nail & KC Remon. tag W. side 14" Quint Tree	N13°E 52.04'
Nail & KC Remon. tag W. side 10" Box Elder	S15°W 0.83'
SW corner garage foundation	N65°E 78.34'
Kent County Monument (H-1, T6N, R10W)	West 63.75'



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 8/25/96