

SURVEY & REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

For corners in SECTION

Kent (County)	Located in: Ada Township	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>10W</u>	<u>I-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 OCT 15 AM 8:51
REG. OF DEEDS
Luci Standa

10213

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on May 29 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1	1831	G.L.O. Notes	Mullett	Set Post
	N/A	Witness Map	K.C. Surveyor	Iron
	1973	L.C.R.C. #531	Exxel Engineering	1/2" Iron
	1984	L.C.R.C. #3955	Exxel Engineering	Fnd. "T" Iron / Set K.C. Monument
	1989	L.C.R.C. #5241	J. Bueche	K.C. Monument

Note: This corner is not common with I-13, T8N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 9/7/84 and was recorded per L.C.R.C. #3955.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/26/97
CHAIRMAN *Randy Kolehouse*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Found a Standard Kent County Monument on the Township line 6' ± West of the C/L of Honey Creek Avenue (bit.) running North and South and 3' ± North of the C/L of 4 Mile Road (gravel) running East and West per L.C.R.C.'s #3955 and #5241 as set by Exxel Engineering in place of a 1/2" iron they found 0.27' South of the Township line which checked L.C.R.C. #531 and the K.C. Surveyor's records.

L.C.R.C. #3955

PK in remon tag at N end curb radius N 40° E 56.34'
Nail & remon tag in W sde 34" Oak S 01° E 174.32'
Nail & remon tag in S sde 24" Oak N 65° W 78.08'

L.C.R.C. #5241

SW cor. Section 35, T8N, R10W (C.I. Mon.) East 199.75'
PK in remon. tag at N end curb radius N 40° E 56.34'
Nail & remon. tag in W side 36" Oak S 01° E 174.32'
Nail & remon. tag in S side 26" Oak N 65° W 78.08' (m. 78.05)

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Standard Kent County Monument

Nail & K.C. remon. tag on N end curb radius N 40° E 56.34'
Nail & K.C. remon. tag on W side 36" Oak S 01° E 174.32'
Nail & K.C. remon. tag on S side 26" Oak N 65° W 78.05'
K.C. Mon. SW 1/4 Sec. 35, T8N, R10W, East 199.75'

Signed by *Randy J. Kolehouse* Date 8-1-97
EARTH TECH
Surveyor's Michigan License No. 25854

