

**SURVEY & REMONUMENTATION**

MAR 03 1998

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

For corners in SECTION

Kent (County)	Located in:	Ada Township	Corner Code #
1. Public Land Survey	T <u>7N</u>	R <u>10W</u>	<u>J-3</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

REG. OF DEEDS

*Luci St. Bond*

97 DEC 15 AM 10:42

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORDING

10370

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on October 7 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-3	1831	G.L.O. Notes	Mullett	Set Post
	N/A	Witness Map	K.C. Surveyor	Iron & Stake
	1973	L.C.R.C. #531	Exxel Engineering	Set "T" Steel Post
	1981	L.C.R.C. #2593	Jonker Land Surveys	Fnd. "T" Fence Post / Set K.C. Monument
	1995	L.C.R.C. #8078	Glaza & Associates	K.C. Monument

P.A. 345 1990 KENT COUNTY,  
 PEER APPROVED 10/30/97  
 CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 12/14/81 and was recorded per L.C.R.C. #2593.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3 Found a Standard Kent County Monument in a swamp Northeast of Chase Lake per L.C.R.C.'s #2593 and #8078 as set by Rob Jonker in place of a "T" fence post he found which checked L.C.R.C. #531.

L.C.R.C. #2593

L.C.R.C. #8078

Remon. tag on N side 14" Ash N 83° E 18.28'  
 Remon. tag on N side 9" Maple S 73° W 9.16'

K.C. remon tag & nail in W side 4" Maple N 03° E 17.59' (m. 17.6')  
 K.C. remon tag & nail in N side 10" Maple (dead) S 70° W 9.12' (m. 9.2')  
 K.C. remon tag & nail in E side 12" Maple S 05° E 30.12' (m. 30.2')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3 Standard Kent County Monument

Nail & K.C. remon. tag on W side 4" Maple N 15° E 14.3'  
 Nail & K.C. remon. tag on NE side 3" Maple S 38° E 5.6'  
 Nail & K.C. remon. tag on N side 4" Maple N 85° E 27.4'  
 Nail & K.C. remon. tag on W side 4" Maple N 03° E 17.6'  
 Nail & K.C. remon. tag on E side 12" Maple S 05° E 30.2'

Signed by

*Randy J. Kolehouse*

Date

11/29/97

EARTH TECH

Surveyor's Michigan License No.

25854

