

SURVEY & REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION

For corners in

For corners in	Located in:	Ada Township	Corner Code #
<u>Kent</u> (County)			
1. Public Land Survey	T <u>7N</u> R <u>10W</u>		<u>J-5</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 OCT 15 AM 8:51
 REG. OF DEEDS
Luigi Bondi

10224

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on May 29 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-5	1831	G.L.O. Notes	Mullett	Set Post
	1961	Witness Map	K.C. Surveyor	Monument Box
	1973	L.C.R.C. #637	Exxel Engineering	3/4" Iron in a Monument Box
	1981	L.C.R.C. #2594	Jonker Land Surveys	Fnd. 3/4" Iron in Mon. Box / Set K.C. Mon. in Mon. Box
	1994	L.C.R.C. #8080	Glaza & Associates	K.C. Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 6/26/97
 CHAIRMAN Gary Huber

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 12/14/81 and was recorded per L.C.R.C. #2594.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5 Found a Standard Kent County Monument 1' ± North of the C/L of 2 Mile Road (bit.) running East and West and 85' East of the C/L of the gravel drive to House #8381 per L.C.R.C.'s #2594 and #8080 as set by Rob Jonker in place of a 3/4" Iron he found in a monument box which checked L.C.R.C. #637 and the K.C. Surveyor's records.

L.C.R.C. #2594

L.C.R.C. #8080

Remon. tag on NE side p. pole S 49° E 71.66'
 Remon. tag on SE side fe. post N 52° E 49.25'
 Remon. tag on W side fe. post N 14° E 34.51'
 Remon. tag on SW side fe. post N 33° W 43.98'
 C/L U.S.G.S. monument S 57° W 59.43'
 C/L U.S.G.S. monument N 65° W 100.02'


K.C. remon tag & nail in SE side fence post N 52° E 49.25'
 K.C. remon tag & nail in W side fence post N 14° E 34.41'
 K.C. remon tag & nail in SW side fence post N 33° W 43.92'
 C/L U.S.G.S. monument S 57° W 59.43'
 C/L U.S.G.S. monument N 65° W 100.02'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 Standard Kent County Monument

Nail & K.C. remon. tag on SE side fence post N 52° E 49.25'
 Nail & K.C. remon. tag on W side fence post N 14° E 34.41'
 Nail & K.C. remon. tag on SW side fence post N 33° W 43.92'
 C/L U.S.G.S. monument S 57° W 59.43'
 C/L U.S.G.S. monument N 65° W 100.02'



Signed by Randy J. Kolehouse
 EARTH TECH

Date 8-1-97

Surveyor's Michigan License No. 25854