

# SURVEY & REMONUMENTATION

**MAR 03 1998**

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

For corners in SECTION  
Kent  
(County)

Located in: Ada Township Corner Code #

- |                                    |             |              |         |  |  |
|------------------------------------|-------------|--------------|---------|--|--|
| 1. Public Land Survey              | T <u>7N</u> | R <u>10W</u> | K-12    |  |  |
|                                    | T _____     | R _____      |         |  |  |
|                                    | T _____     | R _____      |         |  |  |
|                                    | T _____     | R _____      |         |  |  |
| 2. Property Controlling in Section | S _____     | T _____      | R _____ |  |  |
|                                    | S _____     | T _____      | R _____ |  |  |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____      | R _____ |  |  |
|                                    | S _____     | T _____      | R _____ |  |  |

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

97 OCT 15 AM 8:52

REG. OF DEEDS  
*Lucy Bond*  
**10238**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 31 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

|      |      |                |                    |                                     |
|------|------|----------------|--------------------|-------------------------------------|
| K-12 | 1831 | G.L.O. Notes   | Mullett            | Set Post                            |
|      |      | Witness Map    | K.C. Surveyor      | Stone                               |
|      | 1971 | L.C.R.C. #60   | Williams & Works   | Iron & Stone                        |
|      | 1982 | L.C.R.C. #3151 | Moore & Bruggink   | Fnd. 1/2" Rebar / Set K.C. Monument |
|      | 1995 | L.C.R.C. #8095 | Glaza & Associates | K.C. Monument                       |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 5/22/97  
CHAIRMAN *Randy Kolehouse*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Moore & Bruggink on 6/18/82 and was recorded per L.C.R.C. #3151.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-12 Found a Standard Kent County Monument at the corner of remains of fence running South and West per L.C.R.C.'s #3151 and #8095 as set by Moore & Bruggink in place of a 1/2" rebar they found in a 1" iron next to a stone which checked L.C.R.C. #60 and the K.C. Surveyor's records.

**L.C.R.C. #3151**

- KC Nail & Tag 12" Oak N 60° W 24.54'
- KC Nail & Tag 11" Oak N 10° W 26.72'
- KC Nail & Tag 10" Oak East 23.80'
- KC Nail & Tag 9" Oak S 30° E 37.37'
- KC Nail & Tag 5" Oak S 20° W 2.34'

**L.C.R.C. #8095**


- K.C. remon tag & nail in S side 12" Oak N 60° W 24.62' (24.65')
- K.C. remon tag & nail in W side 14" Oak N 10° W 26.74'
- K.C. remon tag & nail in N side 12" Oak East 23.75'
- K.C. remon tag & nail in E side 10" Oak S 30° E 37.37'
- K.C. remon tag & nail in NW side 5" Oak S 20° W 2.34' (2.35')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-12 Standard Kent County Monument

- Nail & K.C. remon. tag on S side 12" Oak N 60° W 24.65'
- Nail & K.C. remon. tag on W side 14" Oak N 10° W 26.74'
- Nail & K.C. remon. tag on N side 12" Oak due East 23.75'
- Nail & K.C. remon. tag on E side 10" Oak S 30° E 37.37'
- Nail & K.C. remon. tag on NW side 5" Oak S 20° W 2.35'



Signed by *Randy J. Kolehouse* Date 5-1-97  
EARTH TECH

Surveyor's Michigan License No. 25854