

FEB 14 1997

KENT COUNTY REMONUMENTATION

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:	Corner Code #
T 7N R 10W	K-13
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 MAR 20 AM 8:49  
REG. OF DEEDS  
*Lucy Bond*

**9020**

Register of Deeds Stamp & File Number

- Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13	1831	GLO	Mullett	Set Post
	1964	Kent Co. Wit.		Iron
	1978	LCRC #1108	Bonnema	1/2" Iron
	1981	LCRC #1770	Merdzinski	Set Kent County Monument
	1995	LCRC #8096	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/7/96  
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/30/81 and was recorded per LCRC #1770

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" Iron he found in a ring of stones. Said Iron checks with Kent Co. Wit. and LCRC #1108.

LCRC #1770 (Nail/tag in trees)	LCRC #8096
24" Oak N20°W 3.44'	18" Oak S25°W 10.03'
12" Oak S80°E 21.03'	8" Oak S30°E 20.95'
8" Maple N60°E 32.58'	
4" Ash S75°W 22.61'	
3/8" Iron West 33.28'	same witnesses ± as LCRC #1770

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Standard Kent County Monument	
Nail & KC Remon. tag E. side 27" Oak	N20°W 3.85'
Nail & KC Remon. tag E. side 22" Oak	S25°W 9.82'
Nail & KC Remon. tag N. side 14" Oak	S80°E 21.20'
Nail & KC Remon. tag NE side 8" Oak	S30°E 20.95'
Nail & KC Remon. tag NW side 8" Maple	N60°E 32.60'
Nail & KC Remon. tag S. side 4" Ash	S75°W 22.47'
Kent Co. Mon. (K-1, T6N, R10W)	West 33.30'
On remains of fence N & W	



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/1/96