

# SURVEY & REMONUMENTATION

MAR 03 1998

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

For corners in  
Kent SECTION  
(County)

Located in: Ada Corner Code #  
Township

- |                                    |             |              |            |
|------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey              | T <u>7N</u> | R <u>10W</u> | <u>L-5</u> |
|                                    | T _____     | R _____      | _____      |
|                                    | T _____     | R _____      | _____      |
|                                    | T _____     | R _____      | _____      |
| 2. Property Controlling in Section | S _____     | T _____      | R _____    |
|                                    | S _____     | T _____      | R _____    |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____      | R _____    |
|                                    | S _____     | T _____      | R _____    |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 OCT 15 AM 8:52  
REG. OF DEEDS  
*Eric Sand*

10241

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 30 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-5	1831	G.L.O. Notes	Mullett	Set Post
	N/A	Witness Map	K.C. Surveyor	Stone
	1967	Witness Map	K.C. Surveyor	Iron
	1972	L.C.R.C. #465	Williams & Works	Iron in Monument Box
	1981	L.C.R.C. #2598	Jonker Land Surveys	Fnd. 3/4" Iron in Mon. Box / Set K.C. Monument in Mon. Box
	1994	L.C.R.C. #8099	Glaza & Associates	K.C. Monument

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		8		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 5/22/97  
CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 12/11/81 and was recorded per L.C.R.C. #2598.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-5 Found a Standard Kent County Monument in a monument box at the C/L intersection of Mc Cabe Avenue (bit.) running North and South and 2 Mile Road (bit.) running East and West per L.C.R.C.'s #2598 and #8099 as set by Rob Jonker in place of a 3/4" iron he found in a monument box over a "T" iron 12" below grade which checked L.C.R.C. #465 and the K.C. Surveyor's records.

L.C.R.C. #2598

L.C.R.C. #8099

SE corner school fnd. (at grd.) N 33° W 67.8'  
C/L of 2" chiseled sq. on N. end conc. culv. N 79° E 81.3'  
On C/L "X" Pavement

Nail & K.C. remon tag in SW side 14" Elm S 61° E 92.84' (92.85')  
SE corner of school foundation (at ground) N 33° W 67.80' (67.82')  
C/L of 2" chiseled sq. on North end conc. culv. N 79° E 81.30' (81.31')  
On C/L intersection of pavement  
Nail & K.C. remon tag in S side 28" Double Oak N 77° W 138.22' (138.25')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-5 Standard Kent County Monument in a Monument Box  
Nail & K.C. remon. tag on SW side 14" Elm S 61° E 92.85'  
Nail & K.C. remon. tag on S side 28" Double Oak N 77° W 138.25'  
SE Cor. school foundation N 33° W 67.82'  
Center line of 2" chisled square on N end conc. culvert N 80° E 81.31'

Signed by Randy J Kolehouse Date 8-1-97  
EARTH TECH

Surveyor's Michigan License No. 25854

