

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION

For corners in

Kent
(County)

Located in: Ada
Township

Corner Code #

- 1. Public Land Survey
T 7N R 10W L-8
- 2. Property Controlling in Section
S T R
- 3. Miscellaneous Property in Sec.
S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 DEC 15 AM 10:42
 REG. OF DEEDS
Lucy St. Grand

10377

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 30 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-8 This corner was not originally set by the G.L.O.

1956	Witness Map	K.C. Surveyor	Iron
1972	L.C.R.C. #348	Williams & Works	3/4" Iron in Monument Box
1975	L.C.R.C. #800	Moore & Bruggink	Monument Box

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 9/25/97
 CHAIRMAN Henry Kubur

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-8 Found a 3/4" pipe in a monument box at the C/L intersection of Conservation Street running East and West and Mc Cabe Avenue (bit.) running North and South per L.C.R.C.'s #348, #800 and the K.C. Surveyor's records. Pipe is 10.9' South and 8.2' East of the intersection of 1/4 lines. Accepted pipe as Center of Section.


K.C. Witness Map - 1956	L.C.R.C. #348	L.C.R.C. #800
16" Oak NE 54.71' (Face)	20" Oak N 55° E 55.72' Cor fe post N 45° W 45.65'	Nail in 18" Oak NE 55.76' Nail in cor. fence post NW 45.65'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-8 Replaced 3/4" Pipe with a Standard Kent County Monument in a Monument Box

Nail on 20" Oak N 55° E 55.72'
 Nail in Cor. fence post N 45° W 45.65'
 Nail & K.C. remon. tag on W side fence post N 40° W 46.43'
 Nail & K.C. remon. tag on W side Power pole N 25° E 82.08'
 Nail & K.C. remon. tag on SE side 22" Oak N 60° E 56.14'
 Nail & K.C. remon. tag on N side 10" Oak S 75° E 114.25'



Signed by Randy J. Kolehouse
 EARTH TECH

Date 11/20/97

Surveyor's Michigan License No. 25854