

# SURVEY & REMONUMENTATION

**MAR 03 1998**

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

For comers in **SECTION**

<u>Kent</u> (County)	Located in: Ada Township	Corner Code #	
1. Public Land Survey	T <u>7N</u> R <u>10W</u>	<u>L-9</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

REG. OF DEEDS

**10243**

Register of Deeds Stamp & File Number

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

97 OCT 15 AM 8:52

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 30 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-9	1831	G.L.O. Notes	Mullett	Set Post
	1944	Witness Map	K.C. Surveyor	Gas Pipe / Monument Box
	1972	L.C.R.C. #348	Williams & Works	3/4" Iron in Monument Box
	1977	L.C.R.C. #1027	Exxel Engineering	3/4" Iron in Monument box
	1981	L.C.R.C. #2599	Jonker Land Surveys	Fnd. 3/4" Iron in Mon. Box / Set K.C. Monument
	1994	L.C.R.C. #8101	Glaza & Associates	K.C. Monument

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 5/22/97  
CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 12/11/81 and was recorded per L.C.R.C. #2599.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-9 Found a Standard Kent County Monument at the C/L of Bailey Drive (bit.) running East, North and West on line of a fence line running South per L.C.R.C.'s #2599 and #8101 as set by Rob Jonker in place of a 3/4" iron he found in a monument box which checked L.C.R.C.'s #1027, #348 and the K.C. Surveyor's records.

**L.C.R.C. #2599**

Remon. tag on W side p. pole S 09° W 49.57'  
Remon. tag on N side fence post S 63° E 51.44'  
Bolt on E end C.M.P. N 19° E 97.55'  
On C/L to E, N, & W & in line fence to South

**L.C.R.C. #8101**

K.C. remon. tag & nail in West side P. pole S 09° W 49.57'  
K.C. remon. tag & nail in North side fence post S 63° E 51.44'  
Bolt on East end of C.M.P. N 19° E 97.55'  
On C/L to E, N & W and in line with fence to South

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-9 Standard Kent County Monument

Nail & K.C. remon. tag on W side Power pole S 09° W 49.57'  
Nail & K.C. remon. tag on N side fence post S 63° E 51.44'  
Bolt on E end C.M.P. N 19° E 97.55'  
Nail & K.C. remon. tag on SE side 8" Spruce S 44° W 63.68'



Signed by Randy J. Kolehouse

Date 8-1-97

Surveyor's Michigan License No. 25854