

\$7.00
\$2.00

SEP 18 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County) Located In: Corner Code #

1. Public Land Survey T 7N R 10W L-12
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

95 JUN 29 AM 11:50

REG. OF DEEDS
Lucy Bond
 8415

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on June 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-12 1837 GLO Not Set
 1951-53 Williams & Works Set & used Iron at "X" 1/4 lines
 1965 Kent Co. Wit. 1/2" Iron
 1976 LCRC #948 Bonnema 1/2" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-12 Found 1/2" Iron Pipe per Kent Co. and LCRC #948 witnesses. Said 1/2" Iron Pipe is 2.6' W. and 0.4' S. of true intersection of 1/4 lines and has been used in many surveys by various surveyors over the years.

Kent Co. Wit.	LCRC #948				
14" Oak ENE 38.08'	10" Oak N 25.91'	P.A. 345	1990	KENT COUNTY	
15" Oak NE 35.34'	16" Oak NW 24.88'	PEER APPROVED	4/27/95		
8" Oak N 26.56'	18" Oak NE 33.92'	CHAIRMAN	<i>Harry Stuber</i>		
17" Oak NW 24.61'	C/L B.T. S 53'				
17" Oak SSW 37.84'					

The 1/2" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-12 Set Standard Kent County Monument in place of the 1/2" Iron Pipe.
 Set Nail & KC Remon. tag S. side 24" Oak N90°W 24.90'
 Set Nail & KC Remon. tag SW side 15" Oak N45°W 25.90'
 Set Nail & KC Remon. tag E. side 20" Oak N20°W 35.37'
 Set Nail & KC Remon. tag E. side 24" Oak N25°E 33.91'
 C/L Asph. Rd. - South 53' m/l



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 6/26/95