

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 MAR 20 AM 8:49
 REG. OF DEEDS
Tim Spauld

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

1. Public Land Survey	T 7N R 10W	L-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

9021

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-13	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Axle
	1977	LCRC #1108	Bonnema	1/2" Iron
	1981	LCRC #1683	Merdzinski	Set Kent County Monument
	1994	LCRC #8103	J. Glaza	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/24/81 and was recorded per LCRC #1683

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" rebar over an Axle he found. Both check with Kent Co. Wit. and LCRC #1108.

<u>LCRC #1683 (Nail/tag in trees)</u>	<u>LCRC #8103</u>
16" Oak N75°W 35.36'	10" Elm N65°E 28.00'
8" Locust N20°W 125.46'	Iron West 16.75'
8" Locust S05°E 49.96'	
24" dbl. Oak S20°E 103.35'	
"+" on culv. S15°W 127.31'	
	Nail/tag 20" Oak N85°W 35.32'
	Nail/tag 14" Elm N65°E 27.68'
	Nail/tag 10" Locust S50°E 49.85'
	Nail/tag 26" dbl. Oak S10°E 103.50'
	KC Mon. (L-1, 6-10) West 16.73'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Standard Kent County Monument			
New Nail & KC Remon. tag S. side	30" Oak	N85°W	35.34'
Nail & KC Remon. tag NW side	16" Elm	N65°E	27.68'
New Nail & KC Remon. tag N. side	10" Locust	S50°E	49.80'
New Nail & KC Remon. tag E. side	28" DbL. Oak	S10°E	103.52'
Nail & KC Remon. tag S. side	10" Locust	S60°E	37.16'
Kent Co. Mon. (L-1, T6N, R10W)		West	16.71'
C/L N-S asph. rd. is	West		6'±



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/1/96