

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filling Requirement of Act 74, Mich. P.A. 1970  
 KENT COUNTY REMONUMENTATION

For corners in **SECTION**

<u>Kent</u> (County)	Located in: <u>Ada</u> Township	Corner Code # <u>M-3</u>
1. Public Land Survey	T <u>7N</u> R <u>10W</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 97 OCT 15 AM 8:52  
 REG. OF DEEDS  
*Lucy Spang*  
**10246**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on June 3 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-3	1831	G.L.O. Notes	Mullett	Set Post
	1940	Witness Map	K.C. Surveyor	Concrete Monument
	1980	L.C.R.C. #1370	Medema, Van Kooten & Assoc.	"T" Iron (A-3, 7TN, R9W)
	1982	L.C.R.C. #3160	Williams & Works	Fnd. "T" Iron / Set K.C. Monument (A-3, T7N, R9W)
	1991	L.C.R.C. #5819	Exxel Engineering	K.C. Monument (A-3, T7N, R9W)
	1994	L.C.R.C. #8048	Glaza & Associates	K.C. Monument (A-3, T7N, R9W)

Note: This corner is common with A-3, T7N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 11/22/82 and was recorded per L.C.R.C. #3160.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-3 Found a Standard Kent County Monument (0.4' below grade) on the C/L of 3 Mile Road (gravel) running East and West and 5' West of the C/L of Boynton Avenue (gravel) running North per L.C.R.C.'s #3160, #5819, #8048 as set by Williams & Works in place of a "T" iron they found which checked L.C.R.C. #1370 and the K.C. Surveyor's records.

L.C.R.C. #3160

L.C.R.C. #8048

Nail & KC Remon tag in SE side 28" Hickory N 45° E 54.96'  
 Nail & KC Remon tag in E side 18" Walnut N 25° W 66.33'  
 Nail & KC Remon tag in S side 12" Oak S 70° W 70.65'  
 Nail & KC Remon tag in NW side 6" Maple S 45° W 33.12'  
 Nail & KC Remon tag in NE side 12" Hickory S 30° E 31.25'  
 Center line of road running North is 5' East of corner

Nail & K.C. remon tag in SE side 30" Hickory N 45° E 54.95' (m. 54.96')  
 Nail & K.C. remon tag in E side 24" Walnut N 21° W 66.33'  
 Nail & K.C. remon tag in NW side 12" Maple S 45° W 33.12'  
 Nail & K.C. remon tag in SE side 14" Hickory S 74° W 70.51'  
 C/L of road running N is 5' E of corner

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.


**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-3 Standard Kent County Monument

Nail & K.C. remon. tag on SE side 30" Hickory N 45° E 54.96'  
 Nail & K.C. remon. tag on E side 24" Walnut N 25° W 66.33'  
 Nail & K.C. remon. tag on NW side 12" Maple S 45° W 33.12'  
 Nail & K.C. remon. tag on S side 14" Hickory S 70° W 70.65'

Signed by Randy J. Kolehouse Date 8-1-97  
 EARTH TECH

Surveyor's Michigan License No. 25854



P.A. 345 1990 KENT COUNTY

PEER APPROVED 5/26/97  
 CHAIRMAN Randy Huber