

SURVEY & REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE 94 DEC -6 AM 8:58

Filing Requirement of Act 74, Mich. P.A. 1970

KENT COUNTY REMONUMENTATION

For corner COMMISSION

W. J. Bond
REG. OF DEEDS

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>A-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7749

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on March 30 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-1	1831	G.L.O. Notes	L. Lyon	P.A. 345 1990 KENT COUNTY
	1944	Wit. Map	K.C. Surveyor	Set Post PEER APPROVED <u>11/17/94</u>
	1973	L.C.R.C. #569	Williams & Works	Conc. Mon. CHAIRMAN <u>Harry Stube</u>
	1982	L.C.R.C. #3169	Jonker	Conc. Mon.
	1990	L.C.R.C. #5435	Starr	Fnd. Conc. Mon./Set K.C. Mon.
				K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Robert Jonker on 11/10/82 and was recorded per L.C.R.C. #3169.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 Found standard Kent County Monument per L.C.R.C. #3169 and #5435 as set by Rob Jonker in place of a 4" x 48" concrete monument he found which checks survey records of K.C. Surveyor 1944 and L.C.R.C. #569.

L.C.R.C. #3169


L.C.R.C. #5435

Remon. tag on W side 36" W. Cherry S 15° W 2.10'	Nail & K.C. remon. tag on W side 36" W. Cherry S 15° W 2.10'
Remon. tag on W side 4" Elm? N 0° E 11.35'	Nail & K.C. remon. tag on W side 4" Elm N 0° E 11.35'
Remon. tag on S side 8" Box Elder S 80° W 7.35'	Nail & K.C. remon. tag on S side 8" Box Elder S 80° W 7.35'
SE cor. septic tank N 75° W 13.67'	SE cor. septic tank N 75° W 13.67'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-1 Standard Kent County Monument
 Nail & K.C. remon. tag on W side 36" W. Cherry S 15° W 2.10'
 Nail & K.C. remon. tag on W side 4" Elm N 0° E 11.35'
 Nail & K.C. remon. tag on S side 8" Box Elder S 80° W 7.35'
 SE cor. septic tank N 75° W 13.67'



Signed by *Randy J. Kolehouse* Date 12/1/94
 Surveyor's Michigan License No. 25854