

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in APR 28 1995

W. J. Bond
REG. OF DEEDS

Kent	Located in:	Corner Code #
<u>COMMISSION</u>		
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>A-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7761
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on July 7 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8 This corner was not originally set by the G.L.O.
1985 L.C.R.C. #4232 William R. Byl Set K.C. Mon.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/11/94
CHAIRMAN Harry Huber

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William R. Byl on 7/8/85 and was recorded per L.C.R.C. #4232.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8 Found standard Kent County Monument per L.C.R.C. #4232 as set by William Byl in place of a concrete monument, bricks and stones he found which checked City of Grand Rapids survey records from 1871-1895.

L.C.R.C. #4232

Nail & tag S side Twin Mulberry S 70° E 7.54'
Kent Co. Monument E 1/4 corner Sec. 24 T7N R12W N 00° W 11.88'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 Standard Kent County Monument
Nail & K.C. remon. tag S side 14" Elder S 65° E 7.54'
Nail & K.C. remon. tag SE side 12" Ash S 48° W 18.46'
Nail & E.T. cap #25854 S side 6" Walnut N 50° W 9.76'
Kent Co. Monument (M-8, T7N, R12W 7/12) North 11.83'



Signed by Randy J. Kolehouse
Surveyor's Michigan License No. 25854

Date 12/11/94