

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 94 DEC 29 AM 11:12

For corners in Kent (County) Located in: Corner Code #

1. Public Land Survey	T <u>7N</u>	R <u>11W</u>	<u>B-6</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Lucy Bond
 REG. OF DEEDS

7945

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on July 5 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6													
6													
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-6 This corner was not originally set by the G.L.O.
 1958 Survey Records Williams & Works City Iron

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 11/3/94
 CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


B-6 Found 2" x 2" City iron in C/L of North Avenue running South 8' North of C/L Sweet Street running E-W which checks Williams & Works survey records of 1958. 2" x 2" Iron is 0.3' North and 3.25' West of intersection of 1/4 line. Accepted 2" x 2" City Iron as Center Section.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-6 Replaced 2" x 2" City iron with Standard 4" x 30" Kent County Monument.

- Nail & K.C. remon. tag in S side 10" Locust N 70° W 30.68'
- Nail & K.C. remon. tag in NW side 10" Ash S 70° W 51.31'
- Nail & K.C. remon. tag in SE side 10" Ash S 25° W 56.42'
- Nail & K.C. remon. tag in N side p. pole N 75° E 20.28'
- Intersection back f sidewalks S 40° E 45.48'



Signed by *Randy J. Kolehouse* Date 12/12/94
 Surveyor's Michigan License No. 25854