

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

Tim Bond
 REG. OF DEEDS

7771

Register of Deeds Stamp & File Number

For corners in

<u>Kent</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>B-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	V
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on July 21 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-9	1831	G.L.O. Notes	Mullett	Set Post
	1949	Survey Notes	Williams & Works	City Iron
	N/A	Survey Notes	City of Grand Rapids	City Iron
	1984	L.C.R.C. #3713	Exxel Engieering	Set Iron in Existing Mon. Box
	1983	L.C.R.C. #4233	William R. Byl	Fnd. Iron in Mon. Box/Set K.C. Mon.
	1988	L.C.R.C. #4600	Bueche	K.C. Mon.

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 11/3/94
 CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William R. Byl on 4/23/85 and was recorded per L.C.R.C. #4233.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9 Found standard Kent County Monument in the C/L of Michigan Street E-W per L.C.R.C.'s #4233 and #4600 as set by William R. Byl in place of an iron in monument box over a 2" x 2" City iron he found which checked Williams & Works and the City of Grand Rapids survey records.

L.C.R.C. #4233

L.C.R.C. #4600

NE cor. fndn. hse. #400 S 40° E 89.28'
 "V" cut in face of conc. light pole S 70° W 67.40'
 Nail & tag W side p. pole N 30° W 38.94'
 E edge manhole rim S 90° W 34.95'

NE cor. fndn. hse. #400 S 40° E 89.28'
 "V" cut in face of conc. light pole S 70° W 67.40'
 Nail & tag W side p. pole N 30° W 38.94'
 E edge manhole rim S 90° W 34.95'
 SW cor. McDonald's bldg. @ brick 5' abv. ground N 45° E 72.78'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9 Standard Kent County Monument
 NE cor. fndn. hse. #400 S 40° E 89.28'
 "V" cut in face of conc. light pole S 70° W 67.40'
 Nail & K.C. remon. tag W side p. pole N 30° W 38.94'
 E edge manhole rim S 90° W 34.95'
 SW cor. McDonald's bldg. @ brick 5' abv. ground N 45° E 72.78'



Signed by Randy J. Kolehouse Date 12/1/94
 Surveyor's Michigan License No. 25854