

**SURVEY & REMONUMENTATION**

APR 28 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD

94 DEC -6 AM 9:00

For corners in

Kent  
 (County)

Located in:

Corner Code #

- |                                    |             |              |             |
|------------------------------------|-------------|--------------|-------------|
| 1. Public Land Survey              | T <u>7N</u> | R <u>11W</u> | <u>B-13</u> |
|                                    | T _____     | R _____      | _____       |
|                                    | T _____     | R _____      | _____       |
|                                    | T _____     | R _____      | _____       |
| 2. Property Controlling in Section | S _____     | T _____      | R _____     |
|                                    | S _____     | T _____      | R _____     |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____      | R _____     |
|                                    | S _____     | T _____      | R _____     |

*Eric J. Bond*  
 REG. OF DEEDS

7773

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on July 21 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-13	1831	G.L.O. Notes	L. Lyon	Set Post
	1930-1957	Survey Records	City of Grand Rapids	City Iron
	1984	L.C.R.C. #3913	William R. Byl	Fnd. City Iron/Set K.C. Mon.
	1988	L.C.R.C. #4670	Bueche	K.C. Monument
	1990	L.C.R.C. #5712	Bueche	Reset K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William R. Byl on 5/21/84 and was recorded per L.C.R.C. #3913.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 Found standard Kent County Monument in the C/L of Hall Street E-W and Madison Avenue N-S per L.C.R.C.'s #3913, #4670 and #5712 as reset by John Bueche at the location of a K.C. monument set by William R. Byl over the top of a City iron in monument box 16" below the road surface.

L.C.R.C. #3913

SE cor. bldg. foundation (@ grade) N 45° W 47.35'  
 SW cor. bldg. foundation SE side of entry (@ grade) N 50° E 49.41'

L.C.R.C. #4670

SE cor. bldg. foundation (@ grade) N 45° W 47.35'  
 SW cor. bldg. foundation SE side of entry (@ grade) N 50° E 49.41'

L.C.R.C. #5712

SE cor. bldg. foundation (@ grade) N 45° W 47.35'  
 SW cor. bldg. foundation SE side of entry (@ grade) N 50° E 49.41'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/3/94

CHAIRMAN

*Harry Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 Standard Kent County Monument  
 SE cor. bldg. foundation (@ grade) N 45° W 47.35'  
 SW cor. bldg. foundation SE side of entry (@ grade) N 50° E 49.41'  
 "<" in top of northernmost of 2 3" conc. filled posts near light pole S 30° W 62.42  
 NE cor. 2x2 conc. pole base S 45° E 81.44'



Signed by Randy J. Kolehouse

Date 12/1/94

Surveyor's Michigan License No. 25854