

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC -6 AM 9:00

Tim J. Bond
REG. OF DEEDS

For corners in

Kent
(County)

Located in:

Corner Code #

- | | | | | |
|------------------------------------|-------------|--------------|-------------|-------|
| 1. Public Land Survey | T <u>7N</u> | R <u>11W</u> | <u>C-13</u> | |
| | T _____ | R _____ | _____ | |
| | T _____ | R _____ | _____ | |
| | T _____ | R _____ | _____ | |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |

7785

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on July 5 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-13	1831	G.L.O. Notes	Mullett	Set Post
	1984	L.C.R.C. #3918	William R. Byl	Fnd. Iron/Set K.C. Mon.
	1988	L.C.R.C. #4671	Bueche	K.C. Mon.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/3/94
CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William R. Byl on 5/21/84 and was recorded per L.C.R.C. #3918.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Found standard Kent County Monument in C/L of Hall Street E-W, at Eastern Avenue North per L.C.R.C.'s #3918 and #4671 as set by William R. Byl in place of a 2"x2" City iron he found which checked City of Grand Rapids survey records.

L.C.R.C. #3918

L.C.R.C. #4671

Nail & tag E side p. pole N 20° W 97.24'
Nail & tag E side p. pole S 35° W 58.57'
NW cor. brick veneer bldg. #1204 S 60° E 106.54'


Nail & tag E side p. pole N 20° W 97.24'
Nail & tag E side p. pole S 35° W 58.57'
NW cor. brick veneer bldg. #1204 S 60° E 106.54'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 Standard Kent County Monument

Nail & K.C. remon. tag E side p. pole N 20° W 97.24'
Nail & K.C. remon. tag E side p. pole S 35° W 58.57'
NW cor. brick veneer bldg. #1204 S 60° E 106.54'
NW cor. square CB N 45° E 50.10"



Signed by Randy J. Kolehouse

Date 12/1/94

Surveyor's Michigan License No. 25854