

# SURVEY & REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

94 DEC -6 AM 9:01

APR 28 1995

For corners in

Kent **COMMISSION** Located in:

Corner Code #

*Lucy Bond*  
REG. OF DEEDS

1. Public Land Survey	T <u>7N</u>	R <u>11W</u>	<u>D-11</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

7790

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	10	9	8	7	6	5	4	3	2	1			
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	39	38	37
13													

I, Randy Kolehouse, in a field survey on June 13 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

D-11	1831	G.L.O. Notes	Mullett	Set Post
	N/A	Survey Records	City of Grand Rapids	City Iron
	1984	L.C.R.C. #3774	William R. Byl	Fnd. P.K./Set K.C. Mon.
	1988	L.C.R.C. #4592	Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/3/94

CHAIRMAN *William R. Byl*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William R. Byl on 2/16/84 and was recorded per L.C.R.C. #3774.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

D-11 Found standard Kent County Monument at Fuller Avenue N-S and Wealthy Street E-W per L.C.R.C.'s #3774 and #4592 as set by William R. Byl in place of a P.K. nail he found which checks street improvements.

L.C.R.C. #3774

L.C.R.C. #4592

Face of hydrant (at walk level) N 55° W 45.05'  
Face of street light pole (at walk level) S 60° E 46.43'  
SW cor. 2'x2' concrete post N 45° E 46.13'  
Nail & tag S side p. pole N 65° E 46.78'  
Face of brick veneer, NE cor. of bldg. #1158  
at S side of entry S 40° W 50.44'


Face of hydrant (at walk level) N 55° W 45.05'  
Face of street light pole (at walk level) S 60° E 46.43'  
SW cor. 2'x2' concrete post N 45° E 46.13'  
Nail & tag S side p. pole N 65° E 46.78'  
Face of brick veneer, NE cor. of bldg. #1158  
at S side of entry S 40° W 50.44'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-11 Standard Kent County Monument

Face of hydrant (at walk level) N 55° W 45.05'  
Face of street light pole (at walk level) S 60° E 46.43'  
SW cor. 2'x2' concrete post N 45° E 46.13'  
Nail & K.C. remon. tag S side p. pole N 65° E 46.78'  
Face of brick veneer, NE cor. of bldg. #1158 at S side of entry S 40° W 50.44'



Signed by *Randy J. Kolehouse*

Date 12/1/94

Surveyor's Michigan License No. 25854