

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC -6 AM 9: 01

For corners in

Kent **COMMISSION** Located in:

Corner Code #

1. Public Land Survey	T <u>7N</u>	R <u>11W</u>	<u>E-6</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Levi Bond
REG. OF DEEDS

7795

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on July 21 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6	1831	G.L.O. Notes	Mullett	Set Post
	1942	Wit. Map	K.C. Surveyor	Stone
	1973	L.C.R.C. #500	Williams & Works	Boat Spike
	1980	L.C.R.C. #1475	Williams & Works	Fnd. Boat Spike/Set K.C. Mon.
	1988	L.C.R.C. #4560	Bueche	K.C. Mon.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94
CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 10/31/80 and was recorded per L.C.R.C. #1475.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found standard Kent County Monument at the C/L of Ball Avenue running N-S and Sweet Street running West per L.C.R.C.'s #1475 and #4560 as set by Williams & Works in place of a boat spike they found which checked one witness L.C.R.C. #500.

L.C.R.C. #1475

Nail & K.C. remon. tag on SW side p. & TV pole N 30° W 39.00'
Nail & K.C. remon. tag on SE side p. & TV pole N 65° E 81.67'
Nail & K.C. remon. tag on SW side guy pole S 45° E 40.47'
SE cor. brick hse. N 50° W 99.30'
NW cor. brick garage S 55° E 120.89'
NE cor. brick hse. S 50° W 86.27'

L.C.R.C. #4560

Nail & K.C. remon. tag on SW side p. & TV pole N 30° W 39.00'
Nail & K.C. remon. tag on SE side p. & TV pole N 65° E 81.67'
Nail & K.C. remon. tag on SW side guy pole S 45° E 40.47'
SE cor. brick hse. N 50° W 99.30'
NW cor. brick garage S 55° E 120.89'
NE cor. brick hse. S 50° W 86.27'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 Standard Kent County Monument
Nail & K.C. remon. tag on SW side p. & TV pole N 30° W 39.00'
Nail & K.C. remon. tag on SE side p. & TV pole N 65° E 81.67'
Nail & K.C. remon. tag on SW side guy pole S 45° E 40.47'
SE cor. brick hse. N 50° W 99.30'
NW cor. brick garage S 55° E 120.70'
NE cor. brick hse. S 50° W 86.27'



Signed by Randy J. Kolehouse Date 12/1/94

Surveyor's Michigan License No. 25854