

# SURVEY & REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC -6 AM 9:01

For comers in

COMMISSION

KENT COUNTY REMONUMENTATION

<u>Kent</u> (County)	Located in:	Corner Code #	
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>E-9</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

*Tracy Bond*  
REG. OF DEEDS

7798

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on July 21 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E-9	1831	G.L.O. Notes	Mullett	Set Post
	1930	Survey Records	City of Grand Rapids	City Iron
	1960	Survey Records	MDOT	Mon. Box
	1977	L.C.R.C. #1018	Williams & Works	Mon. Box
	1985	L.C.R.C. #4242	William R. Byl	Fnd. 1" Iron in Mon. Box/Set K.C. Mon.
	1988	L.C.R.C. #4573	Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/17/99  
CHAIRMAN *[Signature]*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William R. Byl on 1/28/85 and was recorded per L.C.R.C. #4242.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E-9 Found P.K. nail in the C/L of Michigan Street running E-W on C/L of Ball Avenue North and Altens Avenue South per witnesses L.C.R.C.'s #4242 and #4573.

L.C.R.C. #4242

L.C.R.C. #4573

Concrete monument S 30° E 52.23'  
C/L top nut of hydrant S 30° W 49.62'  
"V" cut in face of concrete lt. pole N 30° W 60.31'  
North edge of M.H. rim S 00° W 8.73'

Concrete monument S 30° E 52.23'  
C/L top nut of hydrant S 30° W 49.62'  
"V" cut in face of concrete lt. pole N 30° W 60.31'  
North edge of M.H. rim S 00° W 8.73'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-9 Set Standard Kent County Monument  
Concrete monument S 30° E 52.20'  
C/L top nut of hydrant S 30° W 49.62'  
"V" cut in face of concrete lt. pole N 30° W 60.31'  
North edge of M.H. rim S 00° W 8.65'  
Nail & K.C. remon. tag SE side p. pole 46.38'



Signed by *Randy J. Kolehouse* Date 12/1/99  
Surveyor's Michigan License No. 25854