

# SURVEY & REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

94 DEC -6 AM 9:02

*W. J. Bond*  
REG. OF DEEDS

7804  
Register of Deeds Stamp & File Number

For corners in Kent (County) Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T <u>7N</u>	R <u>11W</u>	<u>F-5</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on June 17 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-5	1831	G.L.O. Notes	Mullett	Set Post
	1954	Wit. Map	K.C. Surveyor	"+" in Pavement
	1979	L.C.R.C. #1276	Medema Van Kooten	Iron in Mon. Box
	1982	L.C.R.C. #2761	Williams & Works	Fnd. Iron/Set K.C. Mon.
	1988	L.C.R.C. #4579	Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/17/94  
CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 2/25/82 and was recorded per L.C.R.C. #2761.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
F-5 Found standard Kent County Monument in the C/L of Knapp Street running E-W in the C/L of Perkins Avenue running South per L.C.R.C. 's #2761 and #4579 as set by Williams & Works in place of a 3/4" iron in monument box which they found which checked 1954 witness map and L.C.R.C. #1276.

L.C.R.C. #2761	L.C.R.C. #4579
Nail & K.C. remon. tag in NW side p. & t. pole S 60° W 56.43'	New nail & K.C. remon. tag in E side p. pole North 58.20'
Nail & K.C. remon. tag in SE side 14" Hickory S 40° W 54.60'	New nail & K.C. remon. tag in E side 52" Oak S 20° W 88.00'
Top C/L hydrant N 70° E 69.09'	Nail & K.C. remon. tag in NW side p. & t. pole S 60° W 56.43'
	Nail & K.C. remon. tag in SE side 14" Hickory S 40° W 54.60'
	Top C/L hydrant N 70° E 69.09'
	Cor. is on C/L of roads E, W, & S & on tree line N

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
F-5 Standard Kent County Monument  
New nail & K.C. remon. tag in E side p. pole North 58.20'  
New nail & K.C. remon. tag in E side 52" Oak S 20° W 88.00'  
Nail & K.C. remon. tag in NW side p. & t. pole S 60° W 56.43'  
Nail & K.C. remon. tag in SE side 14" Hickory S 40° W 54.60'  
Top C/L hydrant N 70° E 69.28'  
Cor. is on C/L of roads E, W, & S & on tree line N



Signed by Randy J. Kolehouse Date 12/1/94  
Surveyor's Michigan License No. 25854