

**SURVEY &
REMONUMENTATION**

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC 29 AM 11:12

For corners in **COMMISSION**

KENT COUNTY REMONUMENTATION

For corners in	Located in:	Corner Code #
<u>Kent</u> (County)		
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>F-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Leif J. Janda
REG. OF DEEDS

7956

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on October 6 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-6 This corner was not originally set by the G.L.O.

1905-1947 Survey Records	Williams & Works	Stake/Iron & Stone
1951-1963 Survey Records	Williams & Works	Mon. Box
1978 L.C.R.C. #1276	Medema VanKooten	Mon. Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-6 Found iron pipe in monument box in C/L of Perkins Avenue running N-S which checks 1940-1956 Williams & Works survey records. This point is 4.3' West and 7.4' South of intersection 1/4 lines. Accepted iron in monument box as Center Section.


P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/17/94
CHAIRMAN *[Signature]*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-6 Replaced 1" iron with Standard 4" x 30" Kent County Monument in a monument box.

- Nail & K.C. remon. tag in NW side 40" Maple S 45° W 48.07'
- Nail & K.C. remon. tag in N side p. pole West 24.67'
- Nail & K.C. remon. tag in E side 36" Maple N 22° W 51.85'
- P.K. nail in S side p. pole East 48.12'
- C/L M.H. North 9.09'



Signed by Randy J. Kolehouse Date 12/12/94
Surveyor's Michigan License No. 25854

