

# SURVEY & REMONUMENTATION

APR 28 1995

## COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>F-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
94 DEC 29 AM 11:13

*Luc J. Bond*  
REG. OF DEEDS

7957

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on June 13 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-8 This corner was not originally set by the G.L.O.

1931	Survey Records	Williams & Works	Set Iron
1931-1976	Survey Records	Williams & Works	Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-8 Found 1" iron pipe in tree row running E-W as set at the intersection of 1/4 lines by Williams & Works in 1931. Williams & Works survey records 1956 show this iron to be 1.1' South of E-W 1/4 line. 1" iron pipe checks measurements to E 1/4, W 1/4 and S 1/4 corner as shown in Williams & Works surveys ± 1.0'. Iron is on N-S 1/4 line and 1.4' South of E-W 1/4 line. Accepted 1" iron as Center Section.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/17/94  
CHAIRMAN *Harold Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-8 Replaced 1" iron with a Standard 4" x 30" Kent County Monument.

Nail & K.C. remon. tag in W side 10" Dogwood N 07° W 30.37'  
Nail & K.C. remon. tag in N side Tri 18" Cherry N 80° W 9.85'  
Nail & K.C. remon. tag in N side Tw 14" Cherry S 55° E 13.57'  
Nail & MDOT remon. tag in E side 14" Ash S 20° E 8.12'  
SW corner bldg. N 40° E 71.12'



Signed by *Randy J. Kolehouse* Date 12/12/94  
Surveyor's Michigan License No. 25854

