

SURVEY & REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC -6 AM 9:02

COMMISSION KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>F-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Eric J. Bond
REG. OF DEEDS

7806

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on June 13 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-9	1831	G.L.O. Notes	Mullett	Set Post
	1930	Wit. Map	K.C. Surveyor	Iron and Hub
	1974	L.C.R.C. #745	Exxel Engineering	Iron in Mon. Box
	1982	L.C.R.C. #2762	Williams & Works	Fnd. 3/4" Iron in Mon. Box/Set K.C. Mon.
	1988	L.C.R.C. #4581	Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/3/94
CHAIRMAN *[Signature]*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 2/24/82 and was recorded per L.C.R.C. #2762.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 Found standard Kent County Monument in the approximate C/L of Michigan Street running E-W per L.C.R.C. #2762 and #4581 as set by Williams & Works in place of a 3/4" iron in monument box they found which checked 1930 witness map and L.C.R.C. #745.

L.C.R.C. #2762

L.C.R.C. #4581


Nail & K.C. remon tag in East side 24" Maple S 31.84'
Nail & K.C. remon. tag in SW side 12" Pine N 30° W 57.10'
Nail & K.C. remon. tag in NE side 14" Ash S 50° E 46.15'
SE cor. wood sign post N 60° E 82.05'
C/L joint Michigan Street N 0.60'
Corner is on tree line South

Nail & K.C. remon tag in East side 24" Maple S 31.84'
Nail & K.C. remon. tag in SW side 14" Pine N 30° W 57.10'
Nail & K.C. remon. tag in NE side 16" Ash S 50° E 46.15'
SE cor. wood sign post N 60° E 82.05'
C/L joint Michigan Street N 0.60'
Corner is on tree line South

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 Standard Kent County Monument
Nail & K.C. remon tag in East side 24" Maple S 31.84'
Nail & K.C. remon. tag in SW side 14" Pine N 30° W 57.10'
Nail & K.C. remon. tag in NE side 16" Ash S 50° E 46.15'
SE cor. wood sign post N 60° E 82.05'
Corner is on tree line South



Signed by Randy J. Kolehouse
Surveyor's Michigan License No. 25854

Date 12/1/94