

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

DEC 16 AM 9:23

For corners in **COMMISSION**

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T 7N R 11W	H-1 (N 1/4 cor, Sec 3)
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*W. J. Glaza*  
REG. OF DEEDS

**7848**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James C. Glaza, in a field survey on December 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- H-1 Not set by G.L.O.
  - 1943 W & W notes ----- iron
  - 1960 Kent Co. Wit. ----- boat spike in iron
  - 1975 LCRC #3230 Bonnema iron
  - 1985 LCRC #4243 Byl set Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on January 31, 1985 and was recorded per LCRC #4243.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- H-1 Found broken Kent Co. Mon. (Harrison) per witnesses from LCRC #4243 as set by William R. Byl in place of an iron he found.
  - LCRC #4243
  - Nail & tag in N side 40" Oak N60°W 62.87'
  - Nail & tag in E side 12" Oak N10°E 48.68'
  - Nail & tag in N side Power Pole S45°E 30.06'
  - Nail & tag in E side 20" Oak S40°E 70.37'
  - Nail & tag in W side 12" Oak S00°W 49.81'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- H-1 Replace broken county mon. with 4"x24" Kent County Monument (Harrison)
  - Nail & K.C. remon tag in N side 40" Oak N63°W 62.83'
  - Set Nail & K.C. remon tag in E side 16" Oak N06°E 40.57'
  - Set Nail & K.C. remon tag in NE side Power pole S50°E 30.38'
  - Set Nail & K.C. remon tag in NE side 20" Oak S42°E 70.38'
  - Set Nail & K.C. remon tag in W side 14" Oak S00°W 49.66'
  - In C/L East-West road

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/12/94  
CHAIRMAN Harry Huber

Signed by James C. Glaza  
Glaza & Associates, Inc.  
Surveyor's Michigan License No. \_\_\_\_\_

40166

Date December 9, 1994

