

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970  
Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC 16 AM 9:23

For corners in

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	H-4 (Center, Sec 10)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. J. Glaza*  
REG. OF DEEDS

7851

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James C. Glaza, in a field survey on December 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-4	This corner not originally set by G.L.O.		
1950-1963	survey records	Williams & Works	iron
1964	survey records	Williams & Works	reset "T" iron
1964-1973	survey records	Williams & Works	"T" iron
1973	survey records	Exxel	"T" iron
1973	LCRC #492	Spicer	"T" iron
1973	LCRC #596	Bonnema	"T" iron
1985	LCRC #4159	Brintnall	"T" iron
1993	survey records	Glaza & Associates	"T" iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-4 Found "T" iron on July 15, 1994. Remaining witnesses checked with those recorded in 1985 (LCRC #4159) by Arthur Brintnall. This iron was 1.8' North and 2.9' East of the intersection of the 1/4 lines. The Kent County Remonumentation Peer Group approved the "T" iron as the center of Section. December 5, 1994, the "T" iron and witnesses were gone due to road construction. Location of the "T" iron was re-established by measurements made to the 1/4 corners on July 15, 1994.

LCRC #4159

N70°W	51.30'	to nail in N side of 14" Oak
N10°W	96.25'	to nail/tag in W side of P. pole
NE	40.38'	to PK in W side of Twin Box Elder
E	40.0'	to monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 9/22/94  
CHAIRMAN *Harry Stuber*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-4 Set 4" x 18" Kent County Monument in bituminous road.

Set K.C. remon tag & nail in N side	8" Oak	N70°W	50.94'
Set K.C. remon tag & nail in E side	P. pole	N17°W	94.37'
Set K.C. remon tag & nail in N side	42" Willow	S69°E	34.84'
Set K.C. remon tag & nail in S side	22" Cherry	N90°W	55.93'
In C/L North-South bit. road			
Wire fence to East			



Signed by *James C. Glaza*  
Glaza & Associates, Inc.

Surveyor's Michigan License No. 40166

December 12, 1994