

SURVEY & REMONUMENTATION

\$7.00
\$2.00

APR 28 1995

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION LAND CORNER RECORDATION CERTIFICATE

94 DEC 16 AM 9:23

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kent County Remonumentation

W. J. Bond
REC. OF DEEDS

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	H-5 (N 1/4 cor, Sec 15)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7852

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James C. Glaza, in a field survey on November 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Date	Surveyor	Monument	Description
H-5 1831	G.L.O.	Mullett	set post
1960	Kent Co. Wit.	-----	small spike
1980	LCRC #3299	Glaza	iron
1985	LCRC #4158	Brintnall	iron
1985	LCRC #4288	Byl	set Kent Co. Mon.
1992	LCRC #6380	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on April 23, 1985 and was recorded per LCRC #4288.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #4288 as set by William R. Byl in place of an iron he found and per witnesses from LCRC #6380.

LCRC #6380	SE corner foundation of house #2783	N45°W	129.68'
	NE corner siding of house #2788 (2' above ground)	S30°W	103.65'
	Nail & tag in E side 24" Hickory	N17°W	97.28'
	Nail & tag in W side 18" Hickory	N14°E	125.99'
	Nail & tag in E side 18" Hickory	S34°E	64.95'
	Nail & tag in E side 24" Walnut	N27°W	114.53'
	Nail & tag in SE side U.P.	S34°W	48.18'
	C/L top nut hyd.	S14°W	96.57'

Mon. is on C/L "X" of N-S bit. and E-W bit. The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 Standard Kent County Monument	SE corner foundation of house #2783	N45°W	129.68'
	NE corner siding of house #2788 (2' above ground)	S30°W	103.65'
	Nail & K.C. remon tag in E side 24" Hickory	N17°W	97.28'
	Nail & K.C. remon tag in W side 18" Hickory	N14°E	125.99'
	Nail & K.C. remon tag in E side 18" Hickory	S34°E	65.00'
	Nail & K.C. remon tag in E side 24" Walnut	N27°W	114.58'
	Nail & K.C. remon tag in SE side U.P.	S34°W	48.20'
	C/L top nut hyd.	S14°W	96.57'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/12/94

CHAIRMAN W. J. Bond

Signed by James C. Glaza
Glaza & Associates, Inc. 40166

Date December 9, 1994

