

SURVEY & REMONUMENTATION
 \$7.00
 \$2.00 APR 28 1995

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 Kent County Remonumentation

94 DEC 16 AM 9:23

For corners in

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T 7N R 11W	H-7 (S 1/4 cor, Sec 15)
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

W. J. Bond
 REG. OF DEEDS

7854

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James C. Glaza, in a field survey on December 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7	1831	G.L.O.	Mullett	set post
	No Date	Kent Co. Wit.	-----	axle
	1971	LCRC #98	Chambers	axle
	1982	LCRC #2770	Merdzinski	set Kent Co. Mon.
	1992	LCRC #6381	Marschall	Kent Co. Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on March 5, 1982 and was recorded per LCRC #2770

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Found broken Kent Co. Mon. (Harrison) per witnesses from LCRC #2770 as set by John A. Merdzinski in place of a rebar he found and per witnesses from LCRC #6381.

LCRC #6381	K.C. remon tag & nail in NE side U.P.	S45°E	54.12'
	K.C. remon tag & nail in SE side U.P.	S18°W	64.28'
	K.C. remon tag & nail in E side 36" Maple	N21°W	67.18'
	Centerline top nut hydrant	N56°E	56.86'


The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7	K.C. remon tag & nail in SE side utility pole	S18°W	64.30'
	K.C. remon tag & nail in E side 36" Maple	N21°W	67.15'
	Set K.C. remon tag & nail in NE side power pole	S40°E	51.14'
	Centerline top nut hydrant	N56°E	56.82'

Corner is on centerline of Bit. E-W and N-S

P.A. 345 1990 KENT COUNTY
 PEER APPROVED *10/12/98*
 CHAIRMAN *Henry Shuber*



Signed by James C. Glaza
 Glaza & Associates, Inc. 40166
 Surveyor's Michigan License No. _____

Date December 5, 1994