

\$7.00
\$2.00

JAN 24 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

COMMISSION

For corners in

Kent
(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>7N</u>	R <u>11W</u>	<u>H-11</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS
Lucy Bond
8876
95 DEC 28 PM 2:18
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on December 7 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-11 1817 G.L.O. Notes L. Lyon Set Post
1915 L. 23 P. 2 Griffens Lake Park Addition No Corner Shown

Note: No other information on record.


P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/17/94
CHAIRMAN *Harry Hubers*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11 Set temporary point using survey records from Williams & Works and Griffens Lake Park Addition, L. 23 of Plat, Page 2 (1915), using the following: Measured between NE corner Section 34 and the NW corner of the NE 1/4 NE 1/4 1,319.22' (Rec. 1,319.10'), doubled this distance West and set point on Section line using NE corner of Section 34 and Section line as shown in Griffen Lake Park Addition dist. H-11 to H-12 = 2,638.45' (G.L.O. = 2,647.26'). Calculated dist. from H-10 - H-12 as 5,285.35' (G.L.O. = 5,294.52'), pro. H-11 - H-12 = 2,642.67' or within 4.22' of point set.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 Set a Standard 4" x 30" Kent County Monument.
Nail & K.C. remon. tag in S side 10" Maple N 85° E 36.85'
Nail & K.C. remon. tag in SW side 12" Maple S 20° E 42.63'
Nail & K.C. remon. tag in SW side 10" Maple N 68° W 11.13'
Nail & K.C. remon. tag in N side Util. pole N 62° W 109.21'



Signed by Randy J. Kolehouse Date 12/22/95
EARTH TECH

Surveyor's Michigan License No. 25854