

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -6 AM 9:05

For corners in **COMMISSION**

Corner	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Lee J. Jand
REG. OF DEEDS

7820

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on March 31 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1831	G.L.O. Notes	Mullett	Set Post	
	1924-1940	Survey Records	Williams & Works	Iron/Monument	P.A. 345 1990 KENT COUNTY
	N/A	Survey Records	City of Grand Rapids	Iron	PEER APPROVED <u>10/12/94</u>
	1985	L.C.R.C. #4239	William R. Byl	Set K.C. Mon.	CHAIRMAN <u>[Signature]</u>
	1991	L.C.R.C. #6383	Marschall	K.C. Monument	

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William R. Byl on 5/13/85 and was recorded per L.C.R.C. #4239.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found standard Kent County Monument in Hall Street running E-W West of Lake Drive running Nw'ly and SE'ly per L.C.R.C.'s #4239 and #6383 as set by William R. Byl using "plats" in the area.

L.C.R.C. #4239

L.C.R.C. #6383


SE cor. steel MBT cabinet @ grade N 10° W 24.73'
NE cor. brick veneer, house # _____, 10' above driveway S 35° W 92.02'
Kent County Monument at N 1/4 cor. Sec. 3, 6-11

Nail & tag E side 28" Maple S 9° W 52.29'
SE cor. steel MBT cabinet @ grade N 10° W 24.75'
Kent County Monument at N 1/4 cor. Sec. 3, 6-11 S 90° W 26.12'
Nail & tag W side 16" Elm S 28° E 51.50'
Top C/L nut hyd. S 58° W 65.68'
NE cor. brick house #2760 10' above driveway S 35° W 92.03'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument
Nail & K.C. remon. tag in E side 28" Maple S 9° W 52.29'
SE cor. steel MBT cabinet @ grade N 10° W 24.75'
Kent County Monument at N 1/4 cor. Sec. 3, 6-11 S 90° W 26.12'
Nail & K.C. remon. tag in W side 16" Elm S 28° E 51.50'
Top C/L nut hyd. S 58° W 65.68'
NE cor. brick house #2760 10' above driveway S 35° W 92.03'



Signed by *Randy J. Kolehouse* Date 12/1/94
Surveyor's Michigan License No. 25854