

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
 Kent County Remonumentation

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 94 DEC 16 AM 9:23

For corners in Kent
 (County)

COMMISSION

Located In:

Corner Code #:

- | | | |
|------------------------------------|--------------------------|-------------------------|
| 1. Public Land Survey | T <u>7N</u> R <u>11W</u> | I-1 (NW cor.,
Sec 2) |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

William R. Byl
 REG. OF DEEDS

7855

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James C. Glaza, in a field survey on November 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1	1831	G.L.O.	Mullett	set post
	1968	Kent Co. Wit.	-----	bolt spike
	1974	LCRC #3229	Bonnema	boat spike
	1983	LCRC #3552	Glaza	bolt spike
	1985	LCRC #4244	Byl	set Kent Co. Mon.
	1988	LCRC #4893	Bueche	Kent Co. Mon.
	1993	LCRC #6741	Roon	set Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on Jan. 31, 1985 and was recorded per LCRC #4244

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #6741 as set by Russell L. Roon. Kent Co. Mon. set in 1985 was destroyed due to road construction.
 LCRC #6741

Cast iron monument	West	62.22'
SE corner of C.B. cover	N15°W	24.90'
NW corner of concrete base	S20°W	40.30'
NE corner of C.B. cover	S15°W	25.73'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Standard Kent County Monument

Cast iron monument	West	62.22'
SE corner of C.B. cover	N15°W	24.90'
NW corner of concrete base	S20°W	40.30'
NE corner of C.B. cover	S15°W	25.46'
SE corner of C.B. cover	N35°E	41.90'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/12/94

CHAIRMAN *James C. Glaza*

Signed by James C. Glaza
 Glaza & Associates, Inc.
 Surveyor's Michigan License No. _____

Date December 9, 1994

40166

