

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

94 DEC -6 AM 9:05

W. J. Bond
 REG. OF DEEDS

For corners in

Kent
 (County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|-------------|--------------|-------------|
| 1. Public Land Survey | T <u>7N</u> | R <u>11W</u> | <u>I-11</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

7824

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on July 6 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11	1831	G.L.O. Notes	Mullett	Set Post
	1900-1960	Survey Records	Williams & Works	Conc. Mon./"T" Iron P.A. 345 1990 KENT COUNTY
	1972	L.C.R.C. #311	MDSH	"T" Fence Post PEER APPROVED 11/3/99
	1984	Survey Records	All Points	Set Rebar CHAIRMAN <i>Harry Huber</i>
	1985	L.C.R.C. #4245	William R. Byl	Fnd. Rebar/Set K.C. Mon.
	1992	L.C.R.C. #6386	Marschall	K.C. Mon.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William R. Byl on 1/15/85 and was recorded per L.C.R.C. #4245.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found standard Kent County Monument per L.C.R.C. #6386 as set by William R. Byl in place of a rebar he found which was set by all points, surveyors using Williams & Works, MDSH and Medema Van Kooten survey records.

L.C.R.C. #4245

L.C.R.C. #6386

No witnesses remain

C/L bottom of 2" gate post (0.5' above grd.) Southerly post N 16° E 147.32'
 C/L bottom of 2" gate post (0.5' above grd.) Northerly post S 57° W 40.51'
 Back of curb of west side of southbound lane East Beltline S 77° E 133.90'
 C/L bottom of end 2" fence post S 32° W 145.11'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Standard Kent County Monument
 C/L bottom of 2" gate post (0.5' above grd.) Southerly post N 16° E 147.32'
 C/L bottom of 2" gate post (0.5' above grd.) Northerly post S 57° W 40.51'
 Back of curb of west side of southbound lane East Beltline S 77° E 133.90'
 C/L bottom of end 2" fence post S 32° W 145.11'



Signed by *Randy J. Kolehouse* Date 12/1/94
 Surveyor's Michigan License No. 25854