

SURVEY & REMONUMENTATION
 \$7.00
 \$2.00
 APR 28 1995

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 94 DEC 16 AM 9:23
W. J. Bond
 REG. OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 Kent County Remonumentation

For corners in **COMMISSION**

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	J-1 (N 1/4 cor, Sec 2)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

7862
 Register of Deeds Stamp & File Number

I, James C. Glaza, in a field survey on November 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1 Not set by G.L.O.				
1973	Kent Co. Wit.	-----		iron
1973	LCRC #555	VanKooten		iron
1983	LCRC #3552	Glaza		iron
1985	LCRC #4246	Byl		set Kent Co. Mon.
1988	LCRC #4894	Bueche		Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on January 31, 1985 and was recorded per LCRC #4246.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC # 4246 as set by William R. Byl in place of iron pipes he found and per witnesses from LCRC #4894.

LCRC #4894

Nail & K.C. remon tag in W side T. pole	S00°E	37.55'
Nail & K.C. remon tag in N side 17" Pine	S45°E	35.67'
Nail & K.C. remon tag in S side 29" Maple	N50°E	31.21'
Nail & K.C. remon tag in E side 32" Hickory	S65°W	55.80'
Nail & K.C. remon tag in S side 29" Hickory	N80°W	98.46'
K.C. Mon. @ S 1/4 cor, Sec 35, T8N, R11W	N90°W	33.06'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Standard Kent County Monument

Nail & K.C. remon tag in W side T. pole	S00°E	37.55'
Set Nail & K.C. remon tag in S side 30" Maple	N50°E	31.17'
Nail & K.C. remon tag in E side 32" Hickory	S65°W	55.80'
Set Nail & K.C. remon tag in S side 24" Hickory	N80°W	98.52'
K.C. Mon. @ S 1/4 cor, Sec 35, T8N, R11W	N90°W	33.06'

P.A. 345 1900 KENT COUNTY
 PEER APPROVED 10/12/94
 CHAIRMAN *Frank Huber*



Signed by James C. Glaza
 Glaza & Associates, Inc.
 Surveyor's Michigan License No. 40166

Date December 8, 1994